


CA2 ON  
WR 610  
19 70



074



Water management in Ontario

Ontario  
Water Resources  
Commission

*O.W.R.C.*  
*Water Pollution*  
District *Survey*  
Engineers  
Branch



WATER POLLUTION SURVEY

of the

CITY OF OSHAWA

1970

### Copyright Provisions and Restrictions on Copying:

This Ontario Ministry of the Environment work is protected by Crown copyright (unless otherwise indicated), which is held by the Queen's Printer for Ontario. It may be reproduced for non-commercial purposes if credit is given and Crown copyright is acknowledged.

It may not be reproduced, in all or in part, for any commercial purpose except under a licence from the Queen's Printer for Ontario.

For information on reproducing Government of Ontario works, please contact ServiceOntario Publications at [copyright@ontario.ca](mailto:copyright@ontario.ca)



CADDO  
K.R. 610  
1970  
104

THE  
ONTARIO WATER RESOURCES  
COMMISSION  
Report on a  
Water Pollution Survey  
of the  
City of Oshawa  
Division of Sanitary Engineering  
District Engineers Branch  
December, 1970

City of Oshawa  
Water Pollution Survey Report

<u>INDEX</u>	<u>PAGE NUMBER</u>
Introduction	1
Oshawa - General	2
Surface Waters	3
Pollution Survey Results	4
Pollution Control	
(i) Municipal	16
(ii) Industrial	18
Summary and Conclusions	19
Recommendations	21
<u>Appendices</u>	
I    Water Quality and Effluent Objectives	
II   Implementation of Water and Sewage Works Programmes	
III  Sample Results - 1970 Tables I - IV - 1958 and 1963 Tables V - VI	
IV   Maps    Oshawa Creek	
V    "       Goodman Creek	
VI   "       St. Julian Drain	
VII  "       Harmony Creek	
VIII "       Farewell Creek	
Key Map	

## Water Pollution Survey

of the

City of Oshawa

### INTRODUCTION

During May 1970, a water pollution survey was made in the City of Oshawa by Commission staff. The purpose of the survey was to review the water quality of the drainage courses in the Oshawa area and to locate potential and existing sources of pollution which could adversely affect the ground and surface water quality.

In 1958, an initial survey was undertaken in the Oshawa area. A subsequent survey was carried out in 1963, to re-assess the water quality and to note any changes. The latest survey re-sampled many of the locations covered in the initial and subsequent survey but a more concentrated effort was made to check the water quality of storm sewer effluents.

Bacteriological and chemical samples were collected from pertinent points in the city. All samples collected were submitted to the OWRC Laboratory in Toronto for examination and analysis. The samples obtained were grab samples and only reflect the conditions at the time of sampling. The results of the laboratory tests performed on the samples submitted have been included in the appendices, along with an interpretation of the chemical analysis and bacteriological examination.

A section has also been included on methods of implementing water and sewage works programmes.

The laboratory results from the first and second survey reports have been appended to this report so a comparison can be made by anyone wishing to review the relative change in the stream water quality. Comments have been restricted to assessing the conditions reflected by the latest sample results and where applicable general comparisons were made with previous survey results.

Interviews were conducted with various officials of the City of Oshawa and their co-operation was very much appreciated.

#### CITY OF OSHAWA

##### General

The City of Oshawa is located on the north shore of Lake Ontario, 32 miles east of the City of Toronto, the Provincial Capital.

The City of Oshawa has a population at the present time of approximately 85,000. The city boundaries, enclosing an area of approximately 22 square miles, have not changed since the time of the initial survey.

Manufacturing industries supply a major portion of the labour force with jobs. The City of Oshawa has a variety of manufacturing industries but the General Motors Corporation Limited predominates the employment picture, employing approximately 21,000 persons.

The City of Oshawa supplies water and sewage services to most of the developed area of the city. The municipal water supply is obtained from Lake Ontario, at a point west of the harbour area. The Oshawa Water Pollution Control Plant utilizes trickling filters to treat the raw sewage received. The effluent from this plant is discharged to Harmony Creek at a point approximately one mile north of the Creek's point of discharge into Lake Ontario.

#### SURFACE WATERS

The Oshawa Creek system and the Harmony Creek system are not being used extensively for recreational purposes. There is some fishing in the headwaters but the use of these streams for swimming and other recreational activities is not prevalent. There are some areas along Oshawa Creek which have been dammed up by youngsters to make suitable swimming areas.

#### Oshawa Creek

The headwaters of Oshawa Creek originate in the vicinity of the Community of Raglan, approximately 6 miles north of the city limits. A major branch, East Oshawa Creek, begins near Mount Carmel and joins the main branch just inside the city limits above Taunton Road. A smaller tributary known as Goodman Creek joins the main branch just north of the Canadian Pacific right-of-way, east of Park Road. In the area of the harbour,

the St. Julian Drain joins Oshawa Creek. The exact source of the St. Julian Drain is not known because north of Bloor Street, the drain is covered and drainage from an extensive system of storm sewers is collected by this drain. The Oshawa Creek system drains an estimated 30,000 acres of land.

### Harmony Creek

The Harmony Creek system is composed of a number of small tributaries which originate within the immediate area of the city. The main branch of Harmony Creek originates west of Mitchell Corners in the fifth concession of Darlington Township. The largest of the tributaries is Farewell Creek which originates just north of the Community of Solina in Darlington Township. Farewell Creek joins the main branch of Harmony Creek just north of Wentworth Street East.

The Dean Avenue Drain is a tributary of Harmony and very similar to the St. Julian Drain. The open section of the Dean Avenue Drain begins just east of Tennyson Avenue and it joins the main branch of Harmony Creek south of Highway 401. The Harmony Creek watershed includes a total drainage area of approximately 25,000 acres.

## POLLUTION SURVEY RESULTS

### General

A summary of all the samples collected during the survey have been tabulated and organized into a set of tables

which have been included in the appendix at the back of the report.

In the following pages the results of the survey are interpreted and specific problem areas are pinpointed. Area maps of each watercourse have been prepared to help locate the specific sampling points. These maps are contained in the appendix along with a key map of the city.

#### Oshawa Creek

Stream samples were collected from 21 locations throughout the length of Oshawa Creek. At the same time 50 outfalls were located and examined as possible sources of contamination.

Conditions throughout the length of the creek have improved generally but in certain instances problems are still evident.

There is considerable deterioration in the water quality of Oshawa Creek as it flows through the city. The problem areas on the creek occur at King Street and Bond Street and between Bloor Street and Wentworth Street.



### Outfalls

The following list of outfalls all contained waste material of either sanitary origin or from industrial waste processes. The following sampling points are indicated on the maps of Oshawa Creek which have been numbered 1 to 7.

#### 0-1.2W

This municipal storm sewer is located opposite the east end of Scugog Avenue. The bacterial sample results were excessive and suggests that sanitary wastes were present in this outfall.

#### 0-1.7W(E)

There are two storm sewers at Wentworth Street but there was only flow in the storm sewer which drains to the east side of Oshawa Creek. The sample results indicate that sanitary wastes maybe gaining access to this storm sewer. The BOD of the effluent was slightly higher than expected and the bacterial results show excessive bacterial values.

#### 0-1.81(A) and 0-1.81(B)

These two outfalls are private outfalls which carry waste waters from the Robson Lang Leathers. Industrial wastes such as chromium and ether solubles were very high.

Excessively high BOD and coliform bacteria count were also indicated.

#### 0-2.2W

This outfall is a municipal storm sewer. An ex-

cessive concentration of chromium was found to be in the effluent from this storm sewer.

0-2.4W

This storm sewer drains to an open ditch on the west side of Oshawa Creek near the corner of Malaga Road and Glen Street. The samples results show excessive coliform bacteria present.

0-2.6W(E) and 0-2.6W(W)

These two storm sewers are located at Bloor Street. The sample results indicate an excessive level of coliform bacteria in the effluent.

0-3.54W

This storm sewer outfall discharges to the east side of Oshawa Creek adjacent to the west end of Lloyd Street. The results indicate the presence of coliform bacteria in excessive numbers.

0-3.6 W(E)

This storm sewer outfall discharges to the west side of Oshawa Creek just south of the John Street Bridge. The effluent BOD was higher than might be expected and the bacteriological results indicated an excessive number of coliform bacteria.

0-4.0W(E)

This storm sewer outfall is located at Bond Street West and the effluent is discharged to the east side of Oshawa Creek. The sample results indicate the presence of both industrial and sanitary wastes. Small amount of Chromium and zinc were present in the effluent and a highly unsatisfactory concentration of lead was also found.

0-4.03I

This is a private outfall located just north of Bond Street West which carries wash water from the Auto-Magic Car Wash to the east side of Oshawa Creek. The effluent contained a very high BOD and the numbers of coliform bacteria were excessive.

0-4.1W

This storm sewer is located at the west end of William Street. The bacteriological report indicates excessive numbers of coliform bacteria in the effluent.

0-4.55W

This storm sewer is located adjacent to Ridgeway Avenue. The effluent from this storm sewer flows through an open ditch to the west side of Oshawa Creek. The high count of coliform bacteria indicates the presence of sanitary wastes.

0-4.6W

This storm sewer outfall is located at the west end of Alexandra Street. The effluent from this storm sewer contained excessive numbers of coliform bacteria.

0-5.5W(E)

This storm sewer outfall is located on the east side of Oshawa Creek at Rossland Road. The bacteriological sample results indicate excessive numbers of coliform bacteria.

The above sampling points are the locations where the most serious problems were noted.

Goodman Creek

Goodman Creek is a branch of Oshawa Creek which drains the western edge of the City of Oshawa. During the survey samples were collected from the creek at 10 different locations. An examination was made of 21 outfalls throughout the length of the creek. The locations of the outfalls are shown on the maps of Goodman Creek which have been appended to this report.

The sample results show unsatisfactory conditions in the northern section of this creek. There are no apparent outfalls in this area which can account for the results, and development is very scattered.

Between Rossland Road and Highway #2 the water quality was very good and there was no major source of contamination reaching the creek. Below Highway #2 gradual deterioration in the stream quality takes place. Here, the adverse effect of discharges to the creek is significant and there is no improvement in the stream quality throughout the remainder of the creek until dilution with Oshawa Creek takes place. No apparent improvement has taken place over the past 12 years.

#### Outfalls

The following list of outfalls had unsatisfactory effluents.

#### OG-3.6W

This storm sewer outfall is located at the south end of Montrave Avenue. The analysis of the samples collected at this sampling point were not particularly unsatisfactory but the visual appearance of this outfall suggested that inadequately treated wastes have been or are discharged at this location from time to time.

#### OG-3.8W

This storm sewer outfall is located just west of Grenfell Street and the effluent is discharged to the north side of Goodman Creek. The BOD of the effluent is not excessive but the BOD level is higher than would be expected.

OG-4.7W(E)

This storm sewer outfall is located at Highway #2. The effluent is discharged to the east side of the creek. The bacteriological report indicates excessive numbers of coliform bacteria.

St. Julian Drain

The St. Julian Drain collects storm water and wastes from a large portion of the central section of the city. For the most part the drain is covered and it is only south of Bloor Street that the drain becomes an open watercourse. During the past years there has been a definite improvement in the water quality of this drainage course, but there continues to be evidence of the presence of industrial and sanitary wastes.

Four stream samples were collected from the open section of the drainage course. The sampling locations are shown on the appended drawing titled "St. Julian Drain".

The condition of the drainage course is very poor. Some improvement can be seen in the stream quality as it approaches the harbour area.

Outfalls

An examination was made of five storm sewer outfalls on the St. Julian Drain. The storm sewer outfall at Waterloo Street had no flow at the time of the survey.

OS-1.1W

This municipal storm sewer is located at Wentworth Street. An excessive amount of solids was evident in the effluent but in other respects the results were generally satisfactory.

OS-1.3W

The municipal storm sewer adjacent to the east end of Conant Street contained evidence of sanitary wastes. The bacteriological report indicated a high total and fecal coliform counts.

OS-1.5W(E) and OS-1.5W(W)

There are two storm sewer outfalls at Bloor Street. Both outfalls show some evidence of sanitary wastes. The bacterial results are high in the east side outfall and in the west side outfall the BOD is quite high and bacterial results are excessive. The presence of industrial-type wastes are indicated in the west outfall. The concentration of zinc and ether solubles are excessive.

Harmony Creek System

During the survey of the Harmony Creek system, 36 stream samples were collected and 61 outfalls were examined. The sampling locations are shown on the drawings of the Harmony Creek system which are appended.



The results of the sampling programme indicate that the water quality of Harmony Creek and tributaries was generally very good. There appears to be a few problems but these are very localized.

Harmony Creek (Main Branch)

The stream water quality of the Main Branch of Harmony Creek was very good. The problems first noted in the 1958 survey report have been corrected for the most part. There were only two problems on the main branch. A total of 8 stream samples were collected and 18 outfalls were examined in this section.

Outfalls

H-0.9T

This outfall is the municipal sewage treatment plant effluent pipe. The sample results indicate an effluent with a high BOD, a high suspended solids concentration, an excessive number of coliform bacteria.

H-4.6W

This outfall is a municipal storm sewer which is located opposite the Oshawa Missionary College north of King Street East. The effluent from this storm sewer had a high BOD.

### Dean Avenue Drain

The Dean Avenue Drain collects storm water from as far north as Wilson Road and Bond Street East. Most of the drain is covered and it is only in the south end that the drain is open. In the initial survey report, there was some evidence of industrial type wastes in this drain. In the 1963 survey report, the problem was not apparent but there was some indication that sanitary wastes were present. The most recent sample results suggest that sanitary wastes are gaining access to this storm sewer.

### Outfalls

#### HD-2.30W(E)

This storm sewer outfall is located at Kingside Park and the effluent is discharged to the north side of the Dean Avenue Drain. Excessive numbers of coliform bacteria were detected in the samples collected.

#### HD-2.30W(W)

This storm sewer outfall is located on the east side of Tennyson Avenue. This outfall marks the end of the closed portion of the Dean Avenue Drain. The bacterial results indicates excessive numbers of coliform bacteria in the effluent.

### Farewell Creek

Farewell Creek only drains a small portion of the City of Oshawa. There is relatively little development in this area.

There was only one outfall draining to the creek and there was no apparent problem.

Harmony Creek (West Branch)

During the survey, eight stream samples were collected from the west branch of Harmony Creek and eleven outfalls were examined. The laboratory results from these samples indicated that the water quality was generally satisfactory. The previous surveys also indicate good water quality.

Harmony Creek (North West Branch)

During the previous surveys there have been some problems in the very north end of this branch. But apparently, the problems have been corrected. There were 27 outfalls examined during the survey and 17 stream samples were collected. There was only one location where the sample results suggest that problems may exist.

Outfall

HWO-5.23W

This storm sewer outfall is located just east of Central Park Boulevard North and north of Volendam Avenue. The bacterial sample results indicate excessive numbers of coliform bacteria in this outfall.

HWO-5.6W

This storm sewer outfall is located at Rossland Road East, west of Wilson Road North. This outfall was not sampled during the month of May when most of the samples were collected because it was not accessible. During November a sample was collected and the BOD was excessive.

Pollution Control

Municipal

The City of Oshawa is served by a municipal sewage treatment and collection system. The sewage treatment plant was constructed in 1955. The present design capacity of existing facilities is 9.0 US MGD. During 1969 the average day flow was 8.1 US MGD. Since the average day flows to the plant are nearing capacity, expansion of the plant has been recommended and the municipality has retained a consultant to do the necessary design. The proposed works include the elimination of the effluent discharge to Harmony Creek by the construction of an outfall pipe to Lake Ontario. Bacterial samples collected at the time of the survey indicated excessive numbers of coliform bacteria in the plant effluent. This was due to problems with disinfection of the effluent. A special study made recently by our Division of Research revealed that the problem is due to inefficiency of the existing chlorination pond in providing disinfection. The proposed new works will include improved chlorination facilities for the plant effluent.

Joint planning by the City of Oshawa and the Town of Whitby will see the construction of a sewage treatment plant at the mouth of Corbett Creek. This will serve the adjoining areas of these two municipalities.

Over the past few years, the City of Oshawa has instituted a correction programme to determine sources of contamination of the storm sewer system and subsequent diversion of these flows to the sanitary sewer system. A number of problems have been corrected on Oshawa Creek.

The municipal sanitary landfill site located in the northern section of the creek's watershed, was responsible for a number of complaints a few years ago. Surface drainage from the site was adversely affecting the stream quality. Steps were taken to prevent runoff to the nearby creek and at present two pumping stations are located on the site and runoff is collected and pumped to the sanitary sewer system.

The City of Oshawa officials initiated a programme whereby the industrial waste loading from each industry to the sewerage system is monitored to protect the sewer system and to prevent an adverse effect on the operation of the municipal sewage treatment plant.

### Industrial

Through co-operation of the local industries with the City of Oshawa and the OWRC, solutions to industrial wastes problems are being developed.

The Robson-Lang Leathers has had the most difficulty in solving their waste disposal problem. The volume and type of wastes from the industry has had a very detrimental effect on the water quality of Oshawa Creek. Robson Lang Leathers has screening, settling, chemical and pH control facilities. At the present time 10% of the waste is being discharged to the sanitary sewers. A sampling programme has been established to determine whether the present treatment reduces the waste to a strength acceptable for discharge to the sanitary sewer system.

In the section of the report which lists the outfalls containing unsatisfactory effluents, the Whiting Avenue Storm Sewer was mentioned. A high concentration of chromium was detected in the effluent sample. The Houdaille Industries Limited has been found to be responsible. In addition to the chromium type wastes present in this storm sewer, a nickel type waste was also being discharged to this sewer. The company has taken steps to reclaim the plating wastes so as to meet the OWRC objectives. Through a sampling programme, the need for further treatment such as neutralization and solids removal will be determined.

A major source of ether solubles and phenols in the St. Julian Drain has been attributed to Duplate Canada Limited. It has been reported that changes in production have been made which will eliminate the oil wastes. A phenol-free coolant is to be used in the glass edging operation and this should reduce the phenol waste problem. Our Division of Industrial Wastes has directed Duplate Canada Limited to stop discharging their coolant to the storm sewer.

A private outfall (0-4.03I) to Oshawa Creek just north of Bond Street belongs to the Auto-Magic Car Wash. The samples collected during the survey showed the effluent from this operation to have a very high BOD, suspended solids concentration and excessive numbers of coliform bacteria. This information has been made known to the owner of the car wash. The problem has been discussed in detail with the owner and he has indicated that he will install the required pumping equipment to deliver all wastes to the sanitary sewer system.

#### SUMMARY AND CONCLUSIONS

A water pollution survey was made of the City of Oshawa during the month of May. This is the third survey report by the Division of Sanitary Engineering. An attempt was made at this time to examine all of the storm sewer outfalls to determine whether any of these discharged waste waters unsuitable for discharge to surface waters.



There has been a general improvement in the stream quality during the past years, but there still exists a number of problems.

There are a number of storm sewers along Oshawa Creek carrying industrial and sanitary wastes. Locating the sources of contamination to the storm sewers will require extensive sampling of the internal storm sewer collection system by the municipality. The most outstanding problem continues to be the effect of waste discharges from Robson Lang Leathers, but efforts by those parties concerned should hopefully be rewarded sometime in the new year. It is anticipated that the new pre-treatment facilities will effectively reduce the strength of the wastes so that discharge to the sanitary sewer system will be permissible.

Good progress has been made in locating and correcting sources of contamination in the St. Julian Drain. Further improvement in the water quality of the drain is expected as additional corrections are made.

Further investigations should be made along Goodman Creek to determine the sources of contamination which are adversely affecting the stream water quality. This will be done by staff during 1971.

The Harmony Creek system has very few problems. The disinfection problem at the sewage treatment plant is probably having the greatest effect on Harmony Creek. The construction

of proposed new facilities should correct this problem.


The municipality has an active programme of pollution abatement, however, much additional work is needed to correct the outstanding problems outlined in this report.

#### RECOMMENDATIONS

The present pollution control programme should be continued and expanded in order to locate and to prevent all sources of untreated and/or inadequately treated wastes from reaching the watercourses.

/jkc

Prepared by:

  
J. A. Clarke,  
Technologist,  
Division of Sanitary Engineering.

APPENDIX I

City of Oshawa

Water Pollution Survey

1970

Water Quality and Effluent Objectives

N.B. A pamphlet entitled

"Guidelines and Criteria

for

Water Quality Management

in

Ontario" has been enclosed

in the map pocket at the back of the report

## APPENDIX I

### WATER QUALITY AND EFFLUENT OBJECTIVES

The OWRC objectives for surface waters is described in a booklet entitled "Guidelines and Criteria for Water Quality Management in Ontario". A copy of the booklet is enclosed in the pocket on the back cover of this report. This publication contains the guidelines and introduces water quality criteria for various uses including public, agricultural and industrial water supply, recreation, aesthetic enjoyment and the propagation of fish and wildlife. The guidelines should be followed to determine the acceptability of a watercourse for various uses.

A few pertinent maximum limits of contaminants in sewage treatment plant and industrial effluents are listed below. Adequate protection for surface waters except in certain specific instances influenced by local conditions, should be provided if the following concentrations and pH range are not exceeded in such effluents.

- 5-Day BOD - not greater than 15 ppm
- Suspended Solids - not greater than 15 ppm
- Phenols - not greater than 20 ppb
- pH - 5.5 to 10.6
- Iron - not greater than 17 ppm
- Ether solubles (Oil) - not greater than 15 ppm

### GLOSSARY OF TERMS

Bacteriological Examinations - The Membrane Filter Technique is used to obtain a direct count of coliform organisms. These

organisms are the normal inhabitants of the intestines of man and other warm-blooded animals and soils. They are always present in large numbers in untreated sewage and are, in general, relatively few in number in other stream pollutants. The fecal portion of the total coliforms originate only in the intestines of man and warm-blooded animals and indicate recent pollution.

Biochemical Oxygen Demand (BOD) - The biochemical oxygen demand test indicates the amount of oxygen required for stabilization of the decomposable organic matter found in sewage, sewage effluent, polluted waters, or industrial wastes, by aerobic biochemical action.

Solids - The analyses for solids include tests for total, suspended and dissolved solids. The total solids is a measure of the solids in solution and in suspension. Suspended solids indicate the measure of undissolved solids of organic or inorganic nature whereas the dissolved solids are a measure of those solids in solution.

Oils and Ether Solubles Materials - These include oils and all other solubles materials such as tarry substances and greases. The presence of these pollutants renders water difficult and sometimes impractical to treat either for industrial or domestic use. Oils make streams unsightly and water unfit for bathing.

Phenolic Compounds - The presence of phenol or phenolic equivalents is generally associated with discharges containing petroleum products, or with wastes from some industries. It

is generally conceded that adequate protection of surface waters will be provided if the concentration of phenols in waste discharges does not exceed 20 parts per billion (ppb). Phenolic type waste can cause objectionable conditions in water supplies and might taint the flesh of fish.

Iron - Water for domestic use should contain less than 0.3 parts per million of iron in order to avoid objectionable tastes, staining and sediment formation. Iron concentrations of not greater than 17 parts per million in waste discharges should permit adequate protection of surface waters.

Chromium - The maximum permissible concentration of hexavalent chromium ( $\text{Cr}^{+6}$ ) for water supplies is 0.05 ppm. Chromium may occur in this form in waste waters from the manufacture of chromates; in chromium plating wastes and as trivalent chromium in chrome tanning liquor. Trivalent chromium ( $\text{Cr}^{+3}$ ) and hexavalent chromium ( $\text{Cr}^{+6}$ ) may exist in water supplies, although the trivalent form rarely occurs in potable water supplies since it precipitates as hydroxide in a neutral or alkaline medium.

Zinc - The allowable zinc level in a water supply is a maximum of 5.0 ppm. In most surface and groundwaters zinc concentrations are present only in trace amounts. Zinc most commonly enters a domestic water supply through waters which have received waste discharges.

Lead - Lead compounds are toxic to all forms of life. They may occur in natural waters or in various industrial and mining effluents. The maximum allowable concentration of lead in potable water is 0.05 ppm.

Cyanide - Cyanides are likely to occur in effluents from gas works and coke ovens, from the scrubbing of gases produced from blast furnaces, in wastes from the surface cleaning of various metals and electroplating processes, and chemical industries. Cyanide in waters is toxic to biological life, the toxicity concentration depending on water quality, temperature and type and size of organism. Fish appear to be greatly affected with values as low as 0.05 ppm being reported toxic to trout. The OWRC Drinking Water Objective is less or equal to 0.01 ppm as  $\text{CN}^-$ .



APPENDIX II

City of Oshawa

Water Pollution Survey

1970

Implementation of Water

and

Sewage Works

Programmes

## APPENDIX II

### IMPLEMENTATION OF WATER AND SEWAGE WORKS PROGRAMMES

Currently, there are three general methods which may be utilized for implementing sewage and water works programmes. These are: 1) to enter into an agreement with the OWRC for the construction of the treatment and collector works with an obligation to pay the debt retirement and operating charges over the term of the agreement with the facility reverting to the municipality at the end of the term of the agreement, 2) by requesting the provision of service from a Provincially-owned project, and 3) by proceeding with the construction independently and meeting capital costs by the sale of debentures.

### OWRC/MUNICIPAL PROJECTS

For the construction of water and sewage works under agreement with this Commission, the works are provided and developed under Sections 39 to 46 of the Ontario Resources Commission Act.

For this type of arrangement, the Commission utilizes a sinking fund and consequently the annual payments are based on a specific debt retirement period and the payments are unchanged for the period of the agreement. This type of

project may be financed over a period of time up to a maximum of thirty years. The annual charges for projects constructed under this agreement are determined as follows:

1. Capital Repayment

As noted, OWRC financing is by the sinking fund method and an annual payment of approximately 2 per cent of the capital cost is required to retire a debt over a thirty-year period.

2. Interest

On new Commission projects, interest is calculated at the current rate.

3. Reserve Fund

To provide money for repairs and replacements, Section 40 of the Ontario Water Resources Commission Act provides for the establishment of a reserve fund by the Commission. It is important to note that this fund is established in the name of the municipality and the balance consequently earns interest. It has now been established by Commission minute that the reserve fund billing for each project shall continue only until the fund reaches an amount of ten times the initial annual billing and the reserve fund billing shall be re-imposed only when the fund has been depleted to 80 per cent or less of the maximum amount.

#### 4. Operating Costs

Under OWRC agreement, the municipality is responsible only for the operating costs directly attributed to the project in the municipality. Therefore, no charges are made by the Commission for the services of head office personnel who are available as required to advise on the satisfactory operation and maintenance of the project.

#### PROVINCIALY-OWNED PROJECTS

In June 1967, the Honourable J. R. Simonett, Minister of Energy and Resources Management, made an announcement which expanded the authorization of this Commission for the provision of water supply and sewage treatment facilities. This new program allows the Commission to construct entire water and sewage works facilities for small municipalities. The capital costs of these can be amortized over a 40 year period.

A slight variation of this programme could be implemented in that the municipality may request that this Commission provide only the major water and sewage works facilities as Provincially-owned works, and develop the water distribution and sewage collector systems under the standard type of Commission project. It would appear that where applicable, it would be more advantageous for the municipality to

proceed on the basis of requesting this Commission to develop entire systems as Provincially-owned works.

The associated cost of supplying these works, including amortization of capital costs, together with operating and maintenance charges, will be recovered by the sale of service to the affected municipalities by rates determined on a usage basis. These facilities will be wholly-owned by the Province of Ontario and the arrangements for service will be formalized by contracts between the Commission and the municipality concerned. The installations will be operated entirely at cost with appropriate provision for adjustment in rate.

#### DEVELOPMENT

If a municipality, after considering the alternatives, wishes this Commission to consider Provincially-financed projects, application forms should be completed and submitted together with a resolution of the Municipal council. A draft of the suggested wording of the resolution is included with the application forms.

If the proposed works are to be built by the municipality on its own initiative or as a formal project under agreement with this Commission, it is required that the Council retain a consulting engineer to prepare preliminary engineering reports on the proposed work. If a Provincial system is con-

templated, no action should be taken with respect to retaining a consulting engineering firm as the Commission will designate a consulting engineer to carry out the Provincial portion of the work and it would be advantageous if the municipal portion be studied and reported on by the same engineer.

**APPENDIX III**

**City of Oshawa**

**Water Pollution Survey**

**1970**

**Sample Results**

**1970 - Tables I - IV**

**1958 and 1963 Tables V - VI**

All analyses reported in ppm  
except where indicated

City of Oshawa  
Water Pollution Survey

Table I(a) Oshawa Creek  
Samples Collected by:  
F. Burford    A. McConnell  
J. Clarke    L. Murray

SAMPLING POINT NO.	LOCATION	DATE	BOD	SOLIDS			BACTERIOLOGICAL EXAMINATION COLIFORM BACTERIA PER 100 ML	
				TOTAL	SUSP.	DISSOLVED	FECAL	TOTAL
0-0.0	OSHAWA CREEK AT HARBOUR MOUTH PH AT LAB - 7.7 CHROMIUM (CR) - 0.0 ZINC (ZN) - 0.01 LEAD (PB) - 0.0 CYANIDE (HCN) - <0.01 ETHER SOLUBLES - TRACE	19/5/70	1.0	270	10	260	104	300
0-0.4	OSHAWA CREEK AT SIMCOE STREET SOUTH PH AT LAB - 7.8 CHROMIUM (CR) - 0.07 ZINC (ZN) - 0.0 LEAD (PB) - 0.0 CYANIDE (HCN) - <0.01 ETHER SOLUBLES - TRACE	19/5/70	6.0	500	20	480	2,000	14,000
0-1.19	OSHAWA CREEK OPPOSITE SCUGOG AVENUE STORM SEWER OUTFALL PH AT LAB - 7.9 CHROMIUM (CR) - 0.08 ZINC (ZN) - 0.04 LEAD (PB) - 0.04 CYANIDE (HCN) - <0.01 ETHER SOLUBLES - 3	19/5/70	6.0	480	30	450	600	43,000
0-1.41	OSHAWA CREEK AT THOMAS STREET PH AT LAB - 7.9 CHROMIUM (CR) - 0.25 ZINC (ZN) - 0.0 LEAD (PB) - 0.04 CYANIDE (HCN) - <0.01 ETHER SOLUBLES - 0	19/5/70	7.5	460	40	420	300	2,300



Table I(a) Cont'd

-2-

SAMPLING POINT NO.	LOCATION	DATE	BOD	SOLIDS			BACTERIOLOGICAL EXAMINATION COLIFORM BACTERIA PER 100 ML	
				TOTAL	SUSP.	DISSOLVED	FECAL	TOTAL
0-1.71	OSHAWA CREEK AT WENTWORTH STREET PH AT LAB - 7.7 CHROMIUM (CR) - 5+ - 50% ZINC (ZN) - 0.0 LEAD (PB) - 0.0 CYANIDE (HCN) - 0.00 ETHER SOLUBLES - 3	19/5/70	22.0	520	60	460	1,100	10,000
0-2.1	OSHAWA CREEK UPSTREAM OF ROBSON LANG LEATHERS PH AT LAB - 8.3 CHROMIUM (CR) - 0.05 ZINC (ZN) - 0.03 LEAD (PB) - 0.0 CYANIDE (HCN) - 0.00 ETHER SOLUBLES - 4	19/5/70	1.4	370	15	355	290	2,600
0-2.21	OSHAWA CREEK UPSTREAM OF WHITING AVENUE STORM SEWER OUTFALL PH AT LAB - 8.6 CHROMIUM (CR) - <0.03 ZINC (ZN) - 0.02 LEAD (PB) - 0.0 CYANIDE (HCN) - 0.00 ETHER SOLUBLES - 2	19/5/70	1.2	390	10	380	260	1,800
0-2.6	OSHAWA CREEK ABOVE BLOOR STREET CHROMIUM (CR) - 0.04 ZINC (ZN) - 0.01 LEAD (PB) - 0.0 CYANIDE (HCN) - <0.1	19/5/70	2.0	360	10	350	390	1,400
0-3.1	OSHAWA CREEK OPPOSITE END OF HIBBERT AVENUE	19/5/70	1.4	360	15	345	220	3,500

Table I(a) Cont'd

-3-

SAMPLING POINT NO.	LOCATION	DATE	BOD	SOLIDS			BACTERIOLOGICAL EXAMINATION COLIFORM BACTERIA PER 100 ML	
				TOTAL	SUSP.	DISSOLVED	FECAL	TOTAL
0-3.2	OSHAWA CREEK ABOVE CONFLUENCE OF GOODMAN CREEK	19/5/70	2.5	330	15	315	320	1,700
0-3.41	OSHAWA CREEK ABOVE GIBB STREET IRON (FE) - 0.45	19/5/70	3.0	350	20	330	---	1,900
0-3.89	OSHAWA CREEK DOWNSTREAM OF KING STREET CHROMIUM (CR) - 0.0 LEAD (PB) - 0.0 CYANIDE (HCN) - 0.00	19/5/70	1.4	390	5	385	---	2,200
0-3.95	OSHAWA CREEK BETWEEN BOND STREET AND KING STREET CHROMIUM (CR) - 0.0 ZINC (ZN) - 0.0 LEAD (PB) - 0.0 CYANIDE (HCN) - <0.01	19/5/70	1.2	540	15	525	1,300	3,600
0-4.15	OSHAWA CREEK EAST OF CIVIC STADIUM	19/5/70	0.8	340	5	335	160	800
0-4.41	OSHAWA CREEK ABOVE ADELAIDE STREET	19/5/70	2.2	330	25	305	70	290
0-5.5	OSHAWA CREEK ABOVE ROSSLAND ROAD	19/5/70	2.0	340	10	330	92	240
0-6.98	OSHAWA CREEK BELOW TAUTON ROAD	19/5/70	1.2	410	5	405	116	900
0-7.02	OSHAWA CREEK ABOVE TAUTON ROAD	19/5/70	1.6	330	10	320	88	148
0-7.28	OSHAWA CREEK ABOVE CONFLUENCE WITH EAST BRANCH	19/5/70	1.6	350	5	345	80	176

Table I(a) Cont'd

-4-

<u>SAMPLING POINT NO.</u>	<u>LOCATION</u>	<u>DATE</u>	<u>BOD</u>	<u>SOLIDS</u>			<u>BACTERIOLOGICAL EXAMINATION COLIFORM BACTERIA PER 100 ML</u>	
				<u>TOTAL</u>	<u>SUSP.</u>	<u>DISSOLVED</u>	<u>FECAL</u>	<u>TOTAL</u>
OE-7.9	OSHAWA CREEK EAST BRANCH AT SIMCOE STREET NORTH	19/5/70	1.2	340	5	335	176	1,200
OE-8.9	OSHAWA CREEK EAST BRANCH AT RITSON ROAD	19/5/70	1.0	310	5	305	136	140

All analyses reported in ppm  
except where indicated

City of Oshawa  
Water Pollution Survey

Table I(b) Outfalls to Oshawa Creek  
Samples Collected by: J. Clarke  
F. Burford  
A. McConnell  
L. Murray

SAMPLING POINT NO.	LOCATION	DATE	BOD	SOLIDS			BACTERIOLOGICAL EXAMINATION COLIFORM BACTERIA PER 100 ML	
				TOTAL	SUSP.	DISSOLVED	FECAL	TOTAL
0-0.41W(S)	STORM SEWER OUTFALL AT SIMCOE STREET SOUTH ON SOUTH WEST SIDE	19/5/70		NO FLOW				
0-0.41D	DRAINAGE DITCH AT SIMCOE STREET SOUTH TO NORTH BANK	19/5/70	2.0	320	5	315	744	2,600
0-0.41W(N)	STORM SEWER OUTFALL AT SIMCOE STREET SOUTH DRAINING TO SWAMP ZINC (ZN) - 0.05	19/5/70	5.0	270	20	250	<4	232
0-0.8W	STORM SEWER OUTFALL AT SOUTH END OF RITSON ROAD	19/5/70	0.6	810	5	805	36	232
0-1.2W	STORM SEWER OUTFALL OPPOSITE THE EAST END OF SCUGOG AVENUE	19/5/70	1.2	960	10	950	1,170	10,800
0-1.4W	STORM SEWER OUTFALL AT THOMAS STREET TO WEST BANK	19/5/70	0.6	1,040	5	1,035	150	2,400
0-1.7W(E)	STORM SEWER OUTFALL AT WENTWORTH STREET TO EAST BANK PH AT LAB - 7.7 ZINC (ZN) - 0.03	19/5/70	8.0	610	5	605	128	8,000
0-1.7W(W)	STORM SEWER OUTFALL AT WENTWORTH STREET TO WEST BANK	19/5/70		NO FLOW				

Table I(b) Cont'd

-2-

SAMPLING POINT NO.	LOCATION	DATE	BOD	SOLIDS			BACTERIOLOGICAL EXAMINATION COLIFORM BACTERIA PER 100 ML	
				TOTAL	SUSP.	DISSOLVED	FECAL	TOTAL
0-1.81(A)	OUTFALL FROM ROBSON LANG LEATHERS PH AT LAB - 8.0 CHROMIUM (CR) - <0.1 ZINC (ZN) - 0.03 LEAD (PB) - 0.0 CYANIDE (HCN) - 0.00 ETHER SOLUBLES - 6	19/5/70	4.5	460	25	435	350	33,000
0-1.811(B)	OUTFALL FROM ROBSON LANG LEATHERS PH AT LAB - 10.6 CHROMIUM (CR) - 8.0 ZINC (ZN) - 0.07 LEAD (PB) - 0.0 CYANIDE (HCN) - 0.00 ETHER SOLUBLES - 34	19/5/70	700	5,560	390	5,170	<100	<100
0-2.2W	STORM SEWER OUTFALL NEAR END OF WHITING AVENUE PH AT LAB - 8.3 CHROMIUM (CR) - 3.1 ZINC (ZN) - 0.08 LEAD (PB) - 0.0 CYANIDE (HCN) - 0.00 ETHER SOLUBLES - 2	19/5/70	3.0	290	10	280	10	140
0-2.4W	STORM SEWER OUTFALL AT CORNER OF MALAGA ROAD AND GLEN STREET CHROMIUM (CR) - 0.0 ZINC (ZN) - 0.0 LEAD (PB) - 0.0 CYANIDE (HCN) - 0.00	19/5/70	2.5	450	10	440	6600	11,400

Table I(b) Cont'd

-3-

SAMPLING POINT NO.	LOCATION	DATE	BOD	SOLIDS			BACTERIOLOGICAL EXAMINATION COLIFORM BACTERIA PER 100 ML	
				TOTAL	SUSP.	DISSOLVED	FECAL	TOTAL
0-2.45W	STORM SEWER OUTFALL AT END OF ERIE STREET	19/5/70			N O	F L O W		
0-2.5W	STORM SEWER OUTFALL AT END OF VALENCIA ROAD CHROMIUM (CR) = 0.04 ZINC (ZN) = 0.0 LEAD (PB) = 0.0 CYANIDE (HCN) = <0.00	19/5/70	1.2	720	25	695	4	3,000
0-2.6W(E)	STORM SEWER OUTFALL AT BLOOR STREET WEST TO EAST BANK CHROMIUM (CR) = 0.03 ZINC (ZN) = 0.0 LEAD (PB) = 0.0 CYANIDE (HCN) = <0.01	19/5/70	2.5	1,280	5	1,275	1,240	9,700
0-2.6W(W)	STORM SEWER OUTFALL AT BLOOR STREET WEST TO WEST BANK CHROMIUM (CR) = 0.06 ZINC (ZN) = 0.25 LEAD (PB) = 0.0 CYANIDE (HCN) = <0.01	19/5/70	1.8	640	5	635	1,100	6,300
0-3.0W	STORM SEWER OUTFALL AT MILL STREET	19/5/70			N O	F L O W		
0-3.17W	STORM SEWER OUTFALL AT END OF SINCLAIR AVENUE	19/5/70			N O	F L O W		
0-3.21W	STORM SEWER OUTFALL AT END OF AVENUE STREET	19/5/70			N O	F L O W		

Table I(b) Cont'd

-4-

SAMPLING POINT NO	LOCATION	DATE	BOD	SOLIDS			BACTERIOLOGICAL EXAMINATION COLIFORM BACTERIA PER 100 ML	
				TOTAL	SUSP.	DISSOLVED	FECAL	TOTAL
0-3.25w	STORM SEWER OUTFALL AT END OF ROYAL STREET	19/5/70		N O F L O W				
0-3.35w	STORM SEWER OUTFALL AT END OF QUEBEC STREET	19/5/70		N O F L O W				
0-3.4w(E)	STORM SEWER OUTFALL AT GIBB STREET TO EAST BANK	19/5/70		N O F L O W				
0-3.4w(W)	STORM SEWER OUTFALL AT GIBB STREET TO WEST BANK	19/5/70		N O F L O W				
0-3.54w	STORM SEWER OUTFALL AT END OF LLOYD STREET	19/5/70	1.0	1,100	5	1,095	--	10,400
0-3.5w(W)	STORM SEWER OUTFALL AT JOHN STREET TO WEST BANK	19/5/70	1.4	1,000	10	1,270	--	2,700
0-3.5w(E)	STORM SEWER OUTFALL AT JOHN STREET TO EAST BANK	19/5/70	9.0	370	10	360	--	6,600
0-3.8w	STORM SEWER OUTFALL AT MIDTOWN DRIVE	19/5/70		NOT SAMPLED - SUBMERGED OUTFALL				
0-3.81w	STORM SEWER OUTFALL ADJACENT TO WEST END OF ATHOL STREET ANIONIC DETERGENTS (ABS) - 2.0	19/5/70	5.0	260	15	245	--	<4
0-3.9w(E)	STORM SEWER OUTFALL AT KING ST TO EAST BANK CHROMIUM (CR) - 0.0 LEAD (PB) - 0.0 CYANIDE (HCN) - 0.00	19/5/70	3.0	1,180	5	1,175	--	2,500

Table I(b) Cont'd

-5-

SAMPLING POINT NO.	LOCATION	DATE	BOD	SOLIDS			BACTERIOLOGICAL EXAMINATION COLIFORM BACTERIA PER 100 ML	
				TOTAL	SUSP.	DISSOLVED	FECAL	TOTAL
0-3.9W(W)	STORM SEWER OUTFALL AT KING STREET WEST TO WEST BANK	19/5/70		NOT SAMPLED - OUTFALL SUBMERGED				
0-4.0W(E)	STORM SEWER OUTFALL AT BOND STREET WEST TO EAST BANK CHROMIUM (CR) - 0.08 ZINC (ZN) - 0.06 LEAD (PB) - 1.4 CYANIDE (HCN) - <0.01 PHENOLS (PPB) - 7 ETHER SOLUBLES - 4	19/5/70	4.5	4,060	70	3,990	1,200	29,000
0-4.0W(W)	STORM SEWER OUTFALL AT BOND STREET WEST TO WEST BANK CHROMIUM (CR) - 0.0 ZINC (ZN) - 0.0 LEAD (PB) - 0.0 CYANIDE (HCN) - <0.01 PHENOLS IN PPB - 6 ETHER SOLUBLES - 4	19/5/70	1.8	950	5	945	80	134,000
0-4.03I	OUTFALL FROM AUTO-MAGIC CAR WASH	19/5/70	220	810	500	310	70	29,000
0-4.1W	STORM SEWER OUTFALL AT END OF WILLIAM STREET CHROMIUM (CR) - 0.04 ZINC (ZN) - 0.0 LEAD (PB) - 0.0 CYANIDE (HCN) - <0.01	19/5/70	1.0	1,060	5	1,055	6,600	12,100
0-4.2W	STORM SEWER OUTFALL AT COLBORNE STREET TO WEST BANK	19/5/70	6.5	770	5	765	36	156



Table I(b) Cont'd

-6-

SAMPLING POINT NO.	LOCATION	DATE	BOD	SOLIDS			BACTERIOLOGICAL EXAMINATION	
				TOTAL	SUSP.	DISSOLVED	COLIFORM BACTERIA PER 100 ML FECAL	TOTAL
0-4.3W	STORM SEWER OUTFALL AT ELGIN STREET TO EAST BANK	19/5/70			NOT LOCATED			
0-4.4W(E)	STORM SEWER OUTFALL AT ADELAIDE STREET WEST TO EAST BANK	19/5/70	2.0	590	10	580	<4	<10
0-4.4W(W)	STORM SEWER OUTFALL AT ADELAIDE STREET WEST TO WEST BANK	19/5/70	1.0	1,180	10	1,170	132	300
0-4.54W	STORM SEWER OUTFALL AT ALMA STREET	19/5/70			NO FLOW			
0-4.55W	STORM SEWER OUTFALL AT RIDGEWAY AVENUE	19/5/70	1.4	1,110	5	1,105	6600	11,400
0-4.6W	STORM SEWER OUTFALL AT ALEXANDRA STREET	19/5/70	5.0	450	5	445	19,000	43,000
0-4.65W	STORM SEWER OUTFALL JUST NORTH OF ALEXANDRA STREET	19/5/70	0.4	530	5	525	4	40
0-4.75W	STORM SEWER OUTFALL AT WALMER ROAD	19/5/70			NO FLOW			
0-5.5W(E)	STORM SEWER OUTFALL AT ROSSLAND ROAD WEST TO EAST BANK	19/5/70	4.0	1,020	10	1,010	24,000	39,000
0-5.5W(W)	STORM SEWER OUTFALL AT ROSSLAND ROAD WEST TO WEST BANK	19/5/70	1.2	930	5	925	8	60
0-5.58W	STORM SEWER OUTFALL WEST OF ANSLE CRESCENT	19/5/70			NO FLOW			
0-5.8W	STORM SEWER OUTFALL SOUTHWEST OF GLENWOOD CRESCENT	19/5/70	1.6	950	5	945	148	4,800

Table I(b) Cont'd

-7-

<u>SAMPLING POINT NO.</u>	<u>LOCATION</u>	<u>DATE</u>	<u>BOD</u>	<u>SOLIDS</u>			<u>BACTERIOLOGICAL EXAMINATION COLIFORM BACTERIA PER 100 ML</u>	
				<u>TOTAL</u>	<u>SUSP.</u>	<u>DISSOLVED</u>	<u>FECAL</u>	<u>TOTAL</u>
0-6.1W	STORM SEWER OUTFALL TO SWITZER DRIVE	19/5/70					<4	40
0-7W	STORM SEWER OUTFALL AT TAUTON ROAD	19/5/70	0.6	1,030	5	1,025	252	3,400
0E-7.3W	STORM SEWER OUTFALL TO EAST BRANCH OF OSHAWA CREEK AT SIMCOE STREET NORTH	19/5/70			NO FLOW			

All analyses reported in ppm  
except where indicated

City of Oshawa

Table II(a) Goodman Creek  
Samples Collected by: F. Burford

Water Pollution Survey

SAMPLING POINT NO.	LOCATION	DATE	BOD	SOLIDS			BACTERIOLOGICAL EXAMINATION	
				TOTAL	SUSP.	DISSOLVED	COLIFORM BACTERIA PER 100 ML FECAL	TOTAL
OG-3.1	GOODMAN CREEK AT CONFLUENCE WITH OSHAWA CREEK	11/5/70	3.0	530	5	525	610	16,000
OG-3.55	GOODMAN CREEK AT PARK ROAD	11/5/70	3.5	500	10	490	440	28,000
OG-4.2	GOODMAN CREEK AT STEVENSON'S ROAD	11/5/70	2.0	410	10	400	16	280
OG-4.69	GOODMAN CREEK SOUTH SIDE OF HIGHWAY 2	11/5/70	0.3	4	10	430	12	1,300
OG-4.71	GOODMAN CREEK NORTH SIDE OF HIGHWAY 2	11/5/70	0.3	430	10	420	12	100
OG-5.55	GOODMAN CREEK AT ADELAIDE STREET	11/5/70	1.0	420	10	410	40	70
OG-6.7	GOODMAN CREEK AT ROSSLAND ROAD	11/5/70	0.4	390	5	385	<4	12
OG-6.8	TRIBUTARY OF GOODMAN CREEK	11/5/70	1.4	440	5	435	104	220
OG-7.94	TRIBUTARY OF GOODMAN CREEK AT THORNTON ROAD	11/5/70	11.0	680	220	460	13,000	44,000
OG-8.3	GOODMAN CREEK AT TAUNTON ROAD	11/5/70	17.0	490	10	480	10	2,400

All analyses reported in ppm  
except where indicated

City of Oshawa

Water Pollution Survey

Outfalls to Goodman Creek  
Table II(b)

Samples Collected by: F. Burford

<u>SAMPLING POINT NO.</u>	<u>LOCATION</u>	<u>DATE</u>	<u>BOD</u>	<u>TOTAL</u>	<u>SOLIDS</u>		<u>BACTERIOLOGICAL EXAMINATION</u>	
					<u>SUSP.</u>	<u>DISSOLVED</u>	<u>COLIFORM BACTERIA PER 100 ML</u>	
							<u>FECAL</u>	<u>TOTAL</u>
OG-3.5W(N)	STORM SEWER OUTFALL AT PARK ROAD TO NORTH BANK	11/5/70			NO FLOW			
OG-3.5W(S)	STORM SEWER OUTFALL AT PARK ROAD TO SOUTH BANK	11/5/70			NO FLOW			
OG-3.6W	STORM SEWER OUTFALL FROM MONTRAVE AVENUE TO NORTH BANK PHENOLS (PPB) - 10	11/5/70	5.5	540	10	530	30	3,300
OG-3.9W	STORM SEWER OUTFALL TO NORTH BANK JUST WEST OF GRENFELL STREET	11/5/70	10.	740	5	735	160	680
OG-4.0W	STORM SEWER OUTFALL TO SOUTH BANK EAST SIDE OF STEVENSON ROAD	11/5/70	---	---	--	---	152	280
OG-4.1W	STORM SEWER OUTFALL TO WEST BANK FROM RADISSON AVENUE	11/5/70			NO FLOW			
OG-4.2W	STORM SEWER OUTFALL AT SOUTHWEST CORNER OF GIBB STREET AND STEVENSON ROAD	11/5/70			NO FLOW			
OG-4.23W(W)	STORM SEWER OUTFALL FROM GIBB STREET TO WEST BANK PHENOLS (PPB) - 15	11/5/70	1.6	490	70	420	10	1,010
OG-4.23W(E)	STORM SEWER OUTFALL AT DURHAM STREET TO EAST BANK	11/5/70			NO FLOW			
OG-4.4W(W)	STORM SEWER OUTFALL AT CARTIER AVENUE TO WEST BANK	11/5/70	1.4	440	15	425	40	750

Table II(b) Cont'd

-2-

<u>SAMPLING POINT NO.</u>	<u>LOCATION</u>	<u>DATE</u>	<u>BOD</u>	<u>SOLIDS</u>			<u>BACTERIOLOGICAL EXAMINATION COLIFORM BACTERIA PER 100 ML</u>	
				<u>TOTAL</u>	<u>SUSP.</u>	<u>DISSOLVED</u>	<u>FECAL</u>	<u>TOTAL</u>
OG-4.4W(E)	STORM SEWER OUTFALL AT CARTIER AVENUE TO EAST BANK	11/5/70			N O	F L O W		
OG-4.6W(W)	STORM SEWER OUTFALL AT MONTCALM AVENUE TO WEST BANK	11/5/70			N O	F L O W		
OG-4.6W(E)	STORM SEWER OUTFALL AT MONTCALM AVENUE TO EAST BANK	11/5/70			N O	F L O W		
OG-4.6W(N)	STORM SEWER OUTFALL AT CABOT STREET TO NORTH BANK	11/5/70			N O	F L O W		
OG-4.7W(W)	STORM SEWER OUTFALL AT HIGHWAY 2 TO WEST BANK	11/5/70			N O	F L O W		
OG-4.7W(E)	STORM SEWER OUTFALL AT HIGHWAY 2 TO EAST BANK	11/5/70	6.0	590	100	490	3,300	80,000
OG-6.0W	STORM SEWER OUTFALL AT END OF RIDGEWAY AVENUE	11/5/70	---	---	--	---	<4	140
OG-6.08W	STORM SEWER OUTFALL AT END OF DUNDEE AVENUE	11/5/70	---	---	--	---	12	200
OG-6.25W	STORM SEWER OUTFALL AT END OF ANNAPOLIS AVENUE	11/5/70	---	---	--	---	52	1,200
OG-8.3W(W)	STORM SEWER OUTFALL AT TAUTON ROAD TO WEST BANK	11/5/70			N O	F L O W		
OG-8.3W(E)	STORM SEWER OUTFALL AT TAUTON ROAD TO EAST BANK	11/5/70	0.6	990	5	985	32	232

All analyses reported in ppm  
except where indicated

City of Oshawa

Table III(a) St. Julian Drain  
Samples Collected by: J. A. Clarke

Water Pollution Survey

SAMPLING POINT NO.	LOCATION	DATE	BOD	SOLIDS			BACTERIOLOGICAL EXAMINATION COLIFORM BACTERIA PER 100 ML	
				TOTAL	SUSP.	DISSOLVED	FECAL	TOTAL
OS-0.5	ST. JULIAN DRAIN AT HARBOUR ROAD PH AT LAB - 7.7 CHROMIUM (CR) - 0.0 ZINC (ZN) - 0.37 LEAD (PB) - 0.0 ETHER SOLUBLES - 5 PHENOLS (PPB) - 0	11/5/70	4.0	650	15	635	280	2,500
OS-0.9	ST. JULIAN DRAIN AT WATERLOO STREET PH AT LAB - 7.9 CHROMIUM (CR) - 0.0 ZINC (ZN) - 0.24 LEAD (PB) - 0.0 ETHER SOLUBLES - 9 PHENOLS (PPB) - 0	11/5/70	5.5	490	15	475	1,700	4,800
OS-1.05	ST. JULIAN DRAIN AT WENTWORTH STREET PH AT LAB - 7.5 CHROMIUM (CR) - 0.0 ZINC (ZN) - 0.32 LEAD (PB) - 0.0 ETHER SOLUBLES - 9 PHENOLS (PPB) - 0	11/5/70	5.0	550	15	535	3,400	4,700
OS-1.2	ST. JULIAN DRAIN BELOW CNR PH AT LAB - 7.5 CHROMIUM (CR) - 0.0 ZINC (ZN) - 0.32 LEAD (PB) - 0.0 ETHER SOLUBLES - 20 PHENOLS (PPB) - 6	11/5/70	13	410	30	380	500	2,900

All analyses reported in ppm  
except where indicated

City of Oshawa  
Water Pollution Survey

Table III(b) Outfalls to  
St. Julian Drain  
Samples Collected by: J. A. Clarke

<u>SAMPLING POINT NO.</u>	<u>LOCATION</u>	<u>DATE</u>	<u>BOD</u>	<u>TOTAL</u>	<u>SOLIDS</u>		<u>BACTERIOLOGICAL EXAMINATION COLIFORM BACTERIA PER 100 ML</u>	
					<u>SUSP.</u>	<u>DISSOLVED</u>	<u>FECAL</u>	<u>TOTAL</u>
OS-0.9W	WATERLOO STREET STORM SEWER OUTFALL	11/5/70			N O F L O W			
OS-1.1W	WENTWORTH STREET STORM SEWER OUTFALL	11/5/70	5.0	1,830	690	1,140	10	80
OS-1.3W	CONANT STREET STORM SEWER OUTFALL	11/5/70	4.0	980	20	960	1,200	1,060,000
OS-1.5W(E)	BLOOR STREET EAST OUTFALL PH AT LAB - 7.6 CHROMIUM (CR) - 0.0 ZINC (ZN) - .14 LEAD (PB) - 0.0 ETHER SOLUBLES - TRACE PHENOLS (PPB) - 8	11/5/70	2.0	1,070	15	1,055	5,400	13,500
OS-1.5W(W)	BLOOR STREET WEST OUTFALL PH AT LAB - 7.4 CHROMIUM (CR) - 0.0 ZINC (ZN) - 5.8 LEAD (PB) - 0.0 ETHER SOLUBLES - 48 PHENOLS (PPB) - 9	11/5/70	38	400	50	350	320	3,100

All analyses reported in ppm  
except where indicated

Samples Collected by:  
F. Burford  
J. A. Clarke

City of Oshawa

Water Pollution Survey

Stream Samples Table IV(a)

Harmony Creek - H

Dean Avenue Branch - Harmony Creek  
- HD

Farewell Creek - HF

West Branch - Harmony Creek - HW

Northwest Branch - Harmony Creek - HW

SAMPLING POINT NO.	LOCATION	DATE	BOD	TOTAL	SOLIDS		BACTERIOLOGICAL EXAMINATION	
					SUSP.	DISSOLVED	COLIFORM BACTERIA PER 100 ML	FECAL TOTAL
H-0.00	HARMONY CREEK (MAIN BR) AT MOUTH CHROMIUM (CR) = 0.0 ZINC (ZN) = 0.12 LEAD (PB) = 0.0	20/5/70	10	540	15	525	11,000	106,000
H-1.1	HARMONY CREEK (MAIN BR) AT WENTWORTH STREET EAST CHROMIUM (CR) = 0.0 ZINC (ZN) = 0.0 LEAD (PB) = 0.0	20/5/70	1.8	530	25	505	92	190
HD-1.95	DEAN AVENUE DRAINAGE COURSE AT BLOOR STREET EAST CHROMIUM (CR) = 0.0 ZINC (ZN) = 0.0 LEAD (PB) = 0.0	20/5/70	1.2	810	5	805	84	192
HD-2.07	DEAN AVENUE DRAINAGE COURSE NORTH OF DEAN AVENUE	20/5/70	0.8	720	5	715	164	700
HF-1.01	FAREWELL CREEK ABOVE WENTWORTH STREET EAST	20/5/70	1.0	400	30	370	76	76
HF-1.70	FAREWELL CREEK AT BLOOR STREET EAST	20/5/70	1.2	350	10	340	56	76
HF-2.16	FAREWELL CREEK AT GRANDVIEW STREET SOUTH	20/5/70	1.0	330	5	325	36	60
HF-2.9	FAREWELL CREEK AT TOWNLINE ROAD SOUTH	20/5/70	1.6	330	5	325	52	80
H-2.98	HARMONY CREEK (MAIN BR) AT OLIVE AVENUE	20/5/70	0.8	450	5	445	36	72



Table IV(a) Cont'd

-2-

<u>SAMPLING POINT NO.</u>	<u>LOCATION</u>	<u>DATE</u>	<u>BOD</u>	<u>SOLIDS</u>			<u>BACTERIOLOGICAL EXAMINATION COLIFORM BACTERIA PER 100 ML</u>	
				<u>TOTAL</u>	<u>SUSP.</u>	<u>DISSOLVED</u>	<u>FECAL</u>	<u>TOTAL</u>
H-3.18	HARMONY CREEK (MAIN BR) BELOW CONFLUENCE OF WEST BRANCH OF HARMONY CREEK	20/5/70	0.8	475	5	470	48	84
H-3.42	HARMONY CREEK (MAIN BR) ABOVE CONFLUENCE OF WEST BRANCH OF HARMONY CREEK	20/5/70	1.0	440	10	430	64	88
H-3.72	HARMONY CREEK (MAIN BR) AT KING STREET EAST	20/5/70	1.0	440	5	435	70	190
H-4.16	A SMALL TRIBUTARY TO HARMONY CREEK (MAIN BR) NEAR LAUREL COURT	20/5/70	0.6	390	5	385	12	96
H-5.14	HARMONY CREEK (MAIN BR) AT TOWNLINE ROAD NORTH	20/5/70	0.8	390	5	385	180	300
H-3.3	HARMONY CREEK (WEST BR) ABOVE CONFLUENCE WITH MAIN BRANCH	20/5/70	0.8	580	5	575	80	390
H-3.98	HARMONY CREEK (WEST BR) BETWEEN KING STREET EAST AND BOND STREET EAST	12/5/70	1.4	520	5	515	<4	800
H-4.12	HARMONY CREEK (WEST BR) NORTH OF BOND STREET EAST	12/5/70	1.0	420	5	415	<4	1,000
H-4.56	HARMONY CREEK (WEST BR) AT ADELAIDE AVENUE EAST	12/5/70	1.2	370	10	360	16	140
H-4.64	HARMONY CREEK (WEST BR) HARMONY ROAD TRIBUTARY	12/5/70	1.0	340	5	335	4	110
H-5.01	HARMONY CREEK (WEST BR) HARMONY ROAD TRIBUTARY, AT HARMONY ROAD NORTH	24/6/70	---	---	--	---	104	1,800

Table IV(a) Cont'd

-3-

SAMPLING POINT NO.	LOCATION	DATE	BOD	SOLIDS			BACTERIOLOGICAL EXAMINATION COLIFORM BACTERIA PER 100 ML	
				TOTAL	SUSP.	DISSOLVED	FECAL	TOTAL
HW-6.00	HARMONY CREEK (WEST BR) HARMONY ROAD TRIBUTARY, ABOVE OSHAWA INDUSTRIAL DISPOSAL SITE	24/6/70	---	---	--	---	1,300	3,300
HW-5.52	HARMONY CREEK (WEST BR) WILSON ROAD TRIBUTARY AT ROSSLAND ROAD EAST	12/5/70	1.0	310	5	305	4	30
HW-4.18	HARMONY CREEK (NORTHWEST BR) ABOVE CONFLUENCE WITH WEST BRANCH	12/5/70	2.0	590	10	580	320	570
HW-4.76	HARMONY CREEK (NORTHWEST BR) AT ADELAIDE AVENUE EAST	12/5/70	2.5	600	15	585	180	500
HW-5.10	HARMONY CREEK (NORTHWEST BR) ABOVE CONFLUENCE WITH MOST WESTERLY TRIBUTARY	12/5/70	1.6	840	140	700	70	700
HW-5.58	HARMONY CREEK (NORTHWEST BR) AT ROSSLAND ROAD EAST	12/5/70	5.0	880	130	750	140	6,400
HW-5.61	HARMONY CREEK (NORTHWEST BR) AT ROSSLAND ROAD EAST	12/5/70	3.0	530	15	515	<4	4,400
HW-5.09	HARMONY CREEK (NORTHWEST BR) END OF VOLENDAM AVENUE	12/5/70	2.5	580	10	570	76	1,800
HW-5.51	HARMONY CREEK (NORTHWEST BR) WEST OF WYCHWOOD STREET	12/5/70	1.4	520	5	515	<4	2,700
HW-5.81	HARMONY CREEK (NORTHWEST BR) SOUTH OF ROSSLAND ROAD	12/5/70	0.8	500	5	495	28	2,500

Table IV(a)

-4-

SAMPLING POINT NO.	LOCATION	DATE	BOD	SOLIDS			BACTERIOLOGICAL EXAMINATION COLIFORM BACTERIA PER 100 ML	
				TOTAL	SUSP.	DISSOLVED	FECAL	TOTAL
HWO-5.91	HARMONY CREEK (NORTHWEST BR) TRIBUTARY NORTH OF ROSSLAND ROAD AND WEST OF RITSON ROAD	12/5/70	0.6	590	5	585	<4	5,700
HWO-6.43	RITSON ROAD TRIBUTARY HARMONY CREEK (NORTHWEST BR)	12/5/70	0.6	570	5	565	<4	72
HWO-6.38	HARMONY CREEK (NORTHWEST BR) AT OSHAWA BOULEVARD NORTH	12/5/70	1.2	540	15	525	40	370
HWO-6.75	HARMONY CREEK (NORTHWEST BR) TRIBUTARY BEHIND MARGIA AVENUE	12/5/70	1.8	470	10	460	12	110
HWO-6.87	HARMONY CREEK (NORTHWEST BR) AT BEATRICE STREET	12/5/70	1.8	780	5	775	180	1,500
HWO-6.93	HARMONY CREEK (NORTHWEST BR) AT NONQUON ROAD	12/5/70	1.4	490	5	485	96	1,200

All analyses reported in ppm  
except where indicated

Samples Collected by:

F. Burford

J. A. Clarke

City of Oshawa

Water Pollution Survey

Outfalls to: Table IV(b)  
Harmony Creek (North West Branch) - HWO  
Harmony Creek (Main Branch) - H  
Dean Avenue Drain - HD  
Farewell Creek - HF  
Harmony Creek (West Branch) - HW

SAMPLING POINT NO.	LOCATION	DATE	BOD	TOTAL	SOLIDS		BACTERIOLOGICAL EXAMINATION COLIFORM BACTERIA PER 100 ML	
					SUSP.	DISSOLVED	FECAL	TOTAL
H-0.9T	MUNICIPAL SEWAGE TREATMENT PLANT OUTFALL CHROMIUM (CR) - 0.0 ZINC (ZN) - 0.9 LEAD (PB) - 0.0	20/5/70	32.0	620	35	585	19,000	230,000
H-1.25W	STORM SEWER OUTFALL AT WENTWORTH STREET	20/5/70	1.0	1,030	5	1,025	24	72
H-1.35W	STORM SEWER OUTFALL AT RALEIGH AVENUE	20/5/70	1.0	510	10	500	<4	<4
HD-2.05W(E)	STORM SEWER EAST SIDE DEAN AVENUE DRAIN ABOVE HIGHWAY 401	20/5/70	1.6	740	5	735	92	1,200
HD-2.05W(W)	STORM SEWER WEST SIDE DEAN AVENUE DRAIN ABOVE HIGHWAY 401	20/5/70	1.2	710	5	705	102	1,100
HD-2.30W	STORM SEWER OUTFALL AT KINGSIDE PARK	20/5/70	1.4	870	10	860	7,800	8,800
HD-2.30W	STORM SEWER OUTFALL AT TENNYSON AVENUE CHROMIUM (CR) - 0.0 ZINC (ZN) - 0.1 LEAD (PB) - 0.0	20/5/70	2.0	670	5	665	48,000	52,000
HF-2.21W	STORM SEWER OUTFALL AT GRANDVIEW STREET SOUTH	20/5/70	1.0	330	5	325	104	108
H-1.90W	STORM SEWER OUTFALL AT BLOOR STREET EAST	20/5/70			NO FLOW			

Table IV(b) Cont'd

-2-

SAMPLING POINT NO	LOCATION	DATE	BOD	SOLIDS			BACTERIOLOGICAL EXAMINATION COLIFORM BACTERIA PER 100 ML	
				TOTAL	SUSP.	DISSOLVED	FECAL	TOTAL
H-2.60W	STORM SEWER OUTFALL AT END OF HARCOURT DRIVE	20/5/70		N O F L O W				
H-2.70W	STORM SEWER OUTFALL WEST OF DIANNE DRIVE	20/5/70	1.8	1,010	5	1,005	60	350
H-2.77W	STORM SEWER OUTFALL EAST OF FLORELL DRIVE	20/5/70		N O F L O W				
H-2.88W	STORM SEWER OUTFALL AT OLIVE AVENUE	20/5/70		GOOD FLOW - UNABLE TO SAMPLE				
H-3.06W	STORM SEWER OUTFALL EAST OF WALNUT COURT	20/5/70	--	--	--	--	16	16
H-3.44W	STORM SEWER OUTFALL AT WEST END OF WILLOWDALE AVENUE	20/5/70	0.8	780	5	755	68	1,300
H-3.72W(E)	STORM SEWER OUTFALL AT KING STREET EAST TO EAST SIDE OF CREEK	20/5/70		N O F L O W				
H-3.72W(W)	STORM SEWER OUTFALL AT KING STREET EAST TO WEST SIDE OF CREEK	20/5/70		N O F L O W				
H-3.82W	STORM SEWER OUTFALL EAST END OF BEAUFORT AVENUE	20/5/70	--	--	--	--	30	960
H-3.98W	STORM SEWER OUTFALL AT REGENT DRIVE	20/5/70		N O F L O W				
H-4.08D	DRAINAGE DITCH AT EAST END OF PARKLANE AVENUE	20/5/70	5.5	810	25	785	<4	<4

Table IV(b) Cont'd

-3-

SAMPLING POINT NO.	LOCATION	DATE	BOD	SOLIDS			BACTERIOLOGICAL EXAMINATION COLIFORM BACTERIA PER 100 ML	
				TOTAL	SUSP.	DISSOLVED	FECAL	TOTAL
H-4.2W	STORM SEWER OUTFALL AT NORTH END OF KEEWATIN STREET	29/5/70	---	---	--	---	4	12
H-4.6W	STORM SEWER OUTFALL OPPOSITE OSHAWA MISSIONARY COLLEGE	20/5/70	30.0	720	15	705	8	1,432
H-4.7W	STORM SEWER OUTFALL AT ROCKCLIFFE STREET	20/5/70	0.6	960	5	955	570	540
HW-3.42W	STORM SEWER OUTFALL AT HARMONY ROAD	12/5/70			NO FLOW			
HW-3.58W	STORM SEWER OUTFALL NORTH OF LINDEN COURT	12/5/70			NO FLOW			
HW-3.62W	STORM SEWER OUTFALL EAST OF FAREWELL STREET SOUTH OF HOSKIN AVENUE	12/5/70			NO FLOW			
HW-3.67W	STORM SEWER OUTFALL AT END OF HOSKIN AVENUE	12/5/70			NO FLOW			
HW-3.84W	STORM SEWER OUTFALL AT EAST END OF ATHOL STREET EAST	12/5/70			NO FLOW			
HW-3.96W(E)	STORM SEWER OUTFALL AT KING STREET EAST TO EAST BANK	12/5/70			NO FLOW			
HW-3.96W(W)	STORM SEWER OUTFALL AT KING STREET EAST TO WEST BANK	12/5/70	---	---	--	---	<4	2,100
HW-4.10W(E)	STORM SEWER OUTFALL AT BOND STREET EAST TO EAST BANK	12/5/70			NO FLOW			
HW-4.10W(W)	STORM SEWER OUTFALL AT BOND STREET EAST TO WEST BANK	12/5/70			NO FLOW			

Table IV(b) Cont'd

-4-

SAMPLING POINT NO.	LOCATION	DATE	BOD	SOLIDS			BACTERIOLOGICAL EXAMINATION COLIFORM BACTERIA PER 100 ML	
				TOTAL	SUSP.	DISSOLVED	FECAL	TOTAL
HW-4.36W	STORM SEWER OUTFALL AT WEST END OF EASTBOURNE AVENUE	12/5/70	0.8	1,060	10	1,050	20	70
HW-4.56W	STORM SEWER OUTFALL AT ADELAIDE AVENUE EAST	12/5/70			N O	F L O W		
HW0-4.38W	STORM SEWER OUTFALL SOUTH OF SUSSEX STREET	12/5/70			N O	F L O W		
HW0-4.50W	STORM SEWER OUTFALL AT WILSON ROAD NORTH	12/5/70			N O	F L O W		
HW0-4.52D	DRAINAGE DITCH WEST SIDE OF WILSON ROAD NORTH	12/5/70	2.0	830	5	825	4	204
HW0-4.58W	STORM SEWER OUTFALL WEST OF LANSDOWNE DRIVE AND WILSON ROAD NORTH	12/5/70			N O	F L O W		
HW0-4.74W	STORM SEWER OUTFALL AT ADELAIDE AVENUE EAST, WEST OF WILSON ROAD SOUTH	12/5/70			N O	F L O W		
HW0-4.96W	STORM SEWER OUTFALL EAST OF ARNHEM DRIVE	12/5/70			N O	F L O W		
HW0-5.06W	STORM SEWER OUTFALL OPPOSITE EAST END OF VOLENDAM AVENUE	12/5/70			N O	F L O W		
HW0-5.38W(E)	STORM SEWER OUTFALL WEST OF BEECHWOOD STREET	12/5/70			N O	F L O W		
HW0-5.38W(W)	STORM SEWER OUTFALL EAST OF BRENTWOOD AVENUE	12/5/70			N O	F L O W		
HW0-5.6W	STORM SEWER OUTFALL AT ROSSLAND ROAD EAST, WEST OF WILSON ROAD NORTH	26/11/70	24.0	2,730	130	2,600	50	2,400

Table IV(b) Cont'd

-5-

SAMPLING POINT NO.	LOCATION	DATE	BOD	SOLIDS			BACTERIOLOGICAL EXAMINATION COLIFORM BACTERIA PER 100 ML	
				TOTAL	SUSP.	DISSOLVED	FECAL	TOTAL
HWO-5.19W	STORM SEWER OUTFALL SOUTH OF REMBRANDT COURT	12/5/70				N O F L O W		
HWO-5.23W	STORM SEWER OUTFALL NORTH OF VOLENDAM AVENUE AND EAST OF CENTRAL PARK BOULEVARD NORTH	12/5/70	6.5	750	50	700	1,600	6,800
HWO-5.27W(E)	STORM SEWER OUTFALL AT CENTRAL PARK BOULEVARD NORTH AND HILLCROFT STREET TO EAST BANK	12/5/70				N O F L O W		
HWO-5.27W(W)	STORM SEWER OUTFALL AT CENTRAL PARK BOULEVARD NORTH AND HILLCROFT STREET TO WEST BANK	12/5/70				N O F L O W		
HWO-5.49W	STORM SEWER OUTFALL EAST OF OSHAWA BOULEVARD NORTH	12/5/70	---	---	--	---	96	1,100
HWO-5.53W	STORM SEWER OUTFALL SOUTH END OF WYCHWOOD STREET	12/5/70				N O F L O W		
HWO-5.65W	STORM SEWER OUTFALL AT END OF HUMEWOOD AVENUE	12/5/70				N O F L O W		
HWO-5.75W	STORM SEWER OUTFALL AT RITSON ROAD NORTH, SOUTH OF ROSSLAND ROAD EAST	12/5/70				N O F L O W		
HWO-5.85W(E)	STORM SEWER OUTFALL AT ROSSLAND ROAD EAST TO EAST BANK	12/5/70				N O F L O W		



Table IV(b) Cont'd

-6-

SAMPLING POINT NO.	LOCATION	DATE	BOD	SOLIDS			BACTERIOLOGICAL EXAMINATION COLIFORM BACTERIA PER 100 ML	
				TOTAL	SUSP.	DISSOLVED	FECAL	TOTAL
HWO-5.85W(W)	STORM SEWER OUTFALL AT ROSSLAND ROAD EAST TO WEST BANK	12/5/70	0.4	810	5	805	236	1,800
HWO-6.09W	STORM SEWER OUTFALL EAST OF OSHAWA BOULEVARD NORTH AND SOUTH OF DARCY STREET	12/5/70	---	---	---	---	20	1,300
HWO-6.17W	STORM SEWER OUTFALL AT DARCY STREET	12/5/70	---	---	---	---	52	510
HWO-6.39W	STORM SEWER OUTFALL AT OSHAWA BOULEVARD NORTH	12/5/70	---	---	---	---	240	280
HWO-6.47W	STORM SEWER OUTFALL NORTH EAST OF ROBERT STREET	12/5/70	1.6	950	5	945	4	120
HWO-6.71W	STORM SEWER OUTFALL END OF MARCIA AVENUE	12/5/70	0.6	460	5	455	40	60
HWO-6.85W	STORM SEWER OUTFALL AT BEATRICE STREET	12/5/70	---	---	---	---	<4	<4
HWO-6.91W	STORM SEWER OUTFALL AT NONQUON ROAD	12/5/70	0.8	1,020	5	1,015	12	570

City of Oshawa

All analyses reported in  
ppm unless otherwise noted

## Water Pollution Survey

Table V  
Summary 1958 and 1963 Survey

SAMPLING POINT NO	DESCRIPTION OF SAMPLING POINTS	DATE	5-DAY BOD	SOLIDS (PPM)			TOTAL COLIFORM	PH	CHROME	
				TOTAL	SUSP	DISS	COUNT PER 100 ML		AS	CR
0-0.0	OSHAWA CREEK AT HARBOUR MOUTH	25/9/58	1.8	212	10	202	1,570			
		12/11/63	2.0	256	12	244	1,100			
0.S.-0.5	ST JULIAN DRAIN AT HARBOUR ROAD	25/9/58	6.5	256	10	246	20,000	11.0		0
	'58 '63	12/11/63	15.0	678	26	652	19,000	7.2		0.02
	ARSENIC (AS) - 0.04	0.0								
	CYANIDE (HCN) - 0	--								
	LEAD (PB) - TRACE	--								
	ETHER SOLUBLES - 19	TRACE								
0.S.-1.3W	CONANT STREET STORM SEWER OUTFALL	25/9/58	50.0	470	14	456	150,000	8.2		0
		12/11/63					700			
0.S.-1.4	ST JULIAN DRAIN BELOW CNR	25/9/58	30.0	344	32	312	2,400	11.1		0
	ARSENIC (AS) - 0.04									
	CYANIDE (HCN) - 0									
	LEAD (PB) - TRACE									
0.S.-1.5	ST JULIAN DRAIN AT BLOOR STREET	25/9/58	39.0	272	30	242	20,000	11.1		0
	'58 '63	12/11/63	62.0	1,200	688	512	1,000	6.9		
	ARSENIC (AS) - 0	--								
	CYANIDE (HCN) - 0	--								
	LEAD (PB) - TRACE	0.4								
	ETHER SOLUBLES - 86	155								
0-0.4	OSHAWA CREEK AT SIMCOE STREET SOUTH	15/10/58	71.0	780	74	706	2,000			
		12/11/63	9.8	426	10	416	6,000			
0-0.41W(N)	STORM DRAIN TO NORTH BANK	15/10/58	2.7	158	6	152	2,500			



Table V Cont'd

-3-

SAMPLING POINT NO	DESCRIPTION OF SAMPLING POINTS	DATE	5-DAY	SOLIDS (PPM)			TOTAL COLIFORM	PH	CHROME	
			BOD	TOTAL	SUSP	DISS	COUNT PER 100 ML		AS	CR
0-2.1	OSHAWA CREEK UPSTREAM OF ROBSON-LANG LEATHERS	15/10/58	3.5	290	6	284	2,400			
		12/11/63	2.1	252	2	250	50			
0-2.2W	STORM SEWER OUTFALL NEAR END OF WHITING AVENUE TO OSHAWA CREEK PHENOLS IN PPB - 30 CYANIDE (HCN) - 0	12/11/63	2.1	262	2	260	30	8.1		0.05
0-2.3W	STORM SEWER FROM CONANT STREET TO OSHAWA CREEK CYANIDE (HCN) - 0 COPPER (CU) - <0.05	12/11/63	1.8	437	7	430	70,000			0.15
0-2.6W(W)	STORM SEWER OUTFALL AT BLOOR STREET WEST TO WEST BANK OF OSHAWA CREEK	15/10/58 12/11/63	2.1	270	16	254	3,000			
					N O F L O W					
0-2.6W(E)	STORM SEWER OUTFALL AT BLOOR STREET WEST TO EAST BANK OF OSHAWA CREEK	15/10/58	1.5	286	12	274	4,000			
		12/11/63	1.3	332	6	326	103,000			
0-2.7	OSHAWA CREEK AT HIGHWAY 401	15/10/58	21.0	294	6	288	1,600			
		12/11/63	2.0	332	3	329	41,000			
06-3.3	GOODMAN CREEK AT NASSAU STREET	16/10/58	1.8	250	12	238	10,000			
		12/11/63	3.0	438	5	433	34,000			
06-4.7W	STORM SEWER TO EAST BANK OF GOODMAN CREEK - NORTH SIDE OF KING STREET	16/10/58	1.0	568	22	546	<10			
		12/11/63	82.0	570	98	472	102,000			
06-4.7	GOODMAN CREEK AT NORTH SIDE OF KING STREET	16/10/58	1.2	360	32	328	640			
		12/11/63	1.6	414	1	413	17,000			
0-3.4W(W)	STORM SEWER TO WEST BANK OF OSHAWA CREEK AT GIBB STREET	16/10/58	54.0	698	68	630	2,000,000			
		12/11/63	18.0	278	5	273	1,890,000			
0-3.6W	STORM SEWER TO EAST BANK OF OSHAWA CREEK NORTH SIDE OF JOHN STREET	16/10/58	11.0	296	62	234	180,000	7.5		
		12/11/63	33.0	592	8	584	16,300			



Table V Cont'd

-5-

SAMPLING POINT NO	DESCRIPTION OF SAMPLING POINTS	DATE	5-DAY	SOLIDS (PPM)			TOTAL COLIFORM	PH	CHROME
			BOD	TOTAL	SUSP	DISS	COUNT PER 100 ML		AS CR
0-5.5	OSHAWA CREEK AT ROSSLAND ROAD WEST	20/10/58	1.1	396	10	386	0		
		12/11/63	2.2	290	2	288	244		
		13/11/63	1.7	314	7	307	170		
0-5.5w(E)	STORM SEWER OUTFALL AT ROSSLAND ROAD WEST TO EAST BANK OF OSHAWA CREEK	20/10/58	2.0	548	6	542	0		
		12/11/63	2.3	528	10	518	900,000		
0-5.5w(W)	STORM SEWER OUTFALL AT ROSSLAND ROAD WEST TO WEST BANK OF OSHAWA CREEK	12/11/63	1.5	612	20	592	290		
0-7.0	OSHAWA CREEK AT TAUNTON ROAD	20/10/58	1.1	260	4	256	0		
		12/11/63	2.0	292	8	284	300		
0E-7.9	EAST BRANCH OF OSHAWA CREEK AT SIMCOE STREET NORTH	20/10/58	1.0	256	12	244	0		
		12/11/63	2.0	300	6	294	40,000		

# Water Pollution Survey

Summary: 1958 and 1963  
Surveys

SAMPLING POINT NO	DESCRIPTION OF SAMPLING POINT	DATE	5-DAY BOD	SOLIDS (PPM)			TOTAL COLIFORM	PH	CHROME
				TOTAL	SUSP	DISS	COUNT PER 100 ML		AS
H-0.0	HARMONY CREEK AT MOUTH	12/11/63	18.0	490	46	444	243,000		
H-0.4	HARMONY CREEK NEAR LAKE ONTARIO DOWN- STREAM FROM STP OUTFALL	23/9/58	33.0	462	54	408	83,000		
H-0.9T	MUNICIPAL SEWAGE TREATMENT PLANT OUTFALL	23/9/58	41.0	408	16	392	500,000		
		12/11/63	54.0	520	34	486	257,000		
HF-1.5	FAREWELL CREEK AT HIGHWAY 401	23/9/58	0.4	228	10	218	200		
		12/11/63	2.3	306	1	305	193		
HF-2.5	FAREWELL CREEK AT TOWNLINE ROAD SOUTH	12/11/63	3.8	302	1	301	73		
HF-3.7	FAREWELL CREEK AT HIGHWAY 2	23/9/58	0.9	278	24	254	40		
HD-1.95	DEAN AVENUE DRAINAGE COURSE AT BLOOR	25/9/58	47.0	400	38	362	300	6.5	9.5
	STREET EAST '58 '63	12/11/63	3.4	346	1	345	19,800	7.9	0.0
	ARSENIC (AS) - 0.06	--							
	CYANIDE (HCN) - TRACE	--							
	PHENOL IN PPB - 20	0							
HD-2.05	DEAN AVENUE DRAINAGE COURSE AT	25/9/58	6.0	380	52	328	300	6.4	2.0
	FAREWELL STREET								
	ARSENIC (AS) - 0.0								
	CYANIDE (HCN) - 0.0								
	PHENOL IN PPB - 18								
HD-2.30W	STORM SEWER OUTFALL AT TENNYSON	25/9/58	13.0	464	68	396	<100	6.8	6.0
	AVENUE								
	ARSENIC (AS) - 0.0								
	CYANIDE (HCN) - 0								
	PHENOL IN PPB - 70								

Table VI Cont'd

-2-

SAMPLING POINT NO	DESCRIPTION OF SAMPLING POINT	DATE	5-DAY	SOLIDS (PPM)			TOTAL COLIFORM COUNT PER 100 ML	PH	CHROME	
			BOD	TOTAL	SUSP	DISS			AS	CR
H-1.7	HARMONY CREEK AT HIGHWAY 401	23/9/58	1.7	504	10	494	400			
		12/11/63	2.5	400	8	392	1,490			
H-3.18	HARMONY CREEK (MAIN BR) BELOW CONFLUENCE OF WEST BRANCH OF HARMONY CREEK	23/9/58	1.2	510	14	496	300			
		12/11/63	2.4	490	4	486	2,600			
H-5.14	HARMONY CREEK (MAIN BR) AT TOWNLINE ROAD NORTH	23/9/58	0.4	428	44	384	490			
		12/11/63	1.7	432	1	431	2,600			
HW-3.98	HARMONY CREEK (WEST BR) AT KING STREET EAST	23/9/58	1.8	480	46	434	300			
		12/11/63	2.1	540	13	527	2,900			
H-4.6DS	SEPTIC TANK EFFLUENT FROM MARACLE PRESS LIMITED TO FLOOD PLAIN OF HARMONY CREEK	23/9/58	50.0	2,200	756	1,444	2,300,000			
H-4.7W	STORM DRAIN FROM MARACLE PRESS LIMITED TO HARMONY CREEK	23/9/58	12.0	282	24	258	<10			
H-4.7W1	DRAIN FROM MARACLE PRESS LIMITED TO HARMONY CREEK (PROCESS WASTE) CYANIDE (HCN) - 3.7 PHENOL IN PPB - TRACE	23/9/58	95.0	1,928	636	1,292	<10	7.4	0	
HW-5.52	HARMONY CREEK (WEST BR) AT ROSSLAND ROAD EAST	24/9/58	1.9	408	46	362	300			
		12/11/63	1.9	357	1	356	2,500			
HW-5.01	HARMONY CREEK (WEST BR) AT HARMONY ROAD	24/9/58	2.0	356	30	326	140			
		28/10/58	1.3	272	8	264	<10			
HW-5.8D	DRAINAGE TO HARMONY CREEK (WEST BR) FROM SITE OF INDUSTRIAL GARBAGE AND DISPOSAL LIMITED ETHER SOLUBLES - 11.3	28/10/58	2.4	476	54	422	<10			



Table VI Cont'd

-3-

SAMPLING POINT NO	DESCRIPTION OF SAMPLING POINT	DATE	5-DAY	SOLIDS (PPM)			TOTAL COLIFORM COUNT PER 100 ML	PH	CHROME	
			BOD	TOTAL	SUSP	DISS			AS	CR
HW-6.00	HARMONY CREEK (WEST BR) AT LITTLE BUCKAROO RANCH	28/10/58	2.4	316	10	306	<10			
HW0-4.5	HARMONY CREEK (NORTHWEST BR) AT WILSON ROAD NORTH NEAR COLBORNE STREET	24/9/58	4.9	600	38	562	60			
		12/11/63	2.1	614	2	612	1,100			
HW0-4.5W(W)	STORM SEWER OUTFALL TO SOUTH BANK OF HARMONY CREEK (NORTHWEST BR) WEST SIDE	24/9/58	0.8	626	40	586	<10			
HW0-4.9D	STORM DRAIN TO HARMONY CREEK (NORTHWEST BR) OPPOSITE IDEAL DAIRY - RITSON ROAD NORTH	24/9/58	3.5	490	38	452	1,000			
		12/11/63	2.3	406	3	403	2,100			
HW0-5.75	HARMONY CREEK (NORTHWEST BR) AT RITSON ROAD NORTH	24/9/58	1.5	440	14	426	740			
		12/11/63	1.5	446	6	440	390			
HW0-5.47W	STORM SEWER OUTFALL NORTHEAST OF ROBERT STREET TO HARMONY CREEK (NORTHWEST BR)	24/9/58	3.1	738	2	736	62,000			
		12/11/63	6.4	412	2	410	7,000			
HW0-6.91	HARMONY CREEK (NORTHWEST BR) NEAR NONQUON ROAD	24/9/58	10.0	986	178	808	80			
		12/11/63	1.4	726	11	715	90			
HW0-6.91W	STORM SEWER OUTFALL NEAR NONQUON ROAD TO HARMONY CREEK (NORTHWEST BR)	12/11/58	2.4	488	42	446	<10			
		12/11/63	9.0	750	86	664	3,100			

APPENDIX IV

City of Oshawa

Water Pollution Survey

1970


Maps

of

Oshawa Creek

Includes: Main Branch

East Branch



### LEGEND

- 0-0.4 - STREAM SAMPLING POINT SHOWING MILEAGE
- 0-0.8 W - OUTFALL SHOWING STREAM AND MILEAGE  
- TYPE OF OUTFALL
- W - STORM SEWER
- D - DRAINAGE DITCH

ONTARIO WATER RESOURCES COMMISSION

### CITY OF OSHAWA OSHAWA CREEK No 1


SCALE: 1050 0 1050 FT.

DRAWN BY: L.L. BROOME

DATE: SEPTEMBER 1970

CHECKED BY: J.C.

DRAWING No: 70-147-DE



### LEGEND

0-1-41 - STREAM SAMPLING POINT SHOWING MILEAGE

0-1-8 I(A) - OUTFALL SHOWING STREAM AND MILEAGE  
- TYPE OF OUTFALL

I - INDUSTRIAL SEWER

W - STORM SEWER


ONTARIO WATER RESOURCES COMMISSION

### CITY OF OSHAWA OSHAWA CREEK No 2

SCALE: 1050 0 1050 FT.

DRAWN BY: L.L. BROOME DATE: OCTOBER, 1970

CHECKED BY: J.C. DRAWING No: 70-154-DE



# **LEGEND**

O-2.6 - STREAM SAMPLING POINT SHOWING MILEAGE

O-3.0 - OUTFALL SHOWING STREAM AND MILEAGE  
W - TYPE OF OUTFALL

W - STORM SEWER

ONTARIO WATER RESOURCES COMMISSION

CITY OF OSHAWA  
OSHAWA CREEK  
No 3


SCALE: 1050 0 1050 FT.

DRAWN BY: L.L. BROOME

DATE: OCTOBER 1970

CHECKED BY: J.C.

DRAWING No: 70-153-DE



### LEGEND

- 0-3.95 - STREAM SAMPLING POINT SHOWING MILEAGE
- 0-4.03 I - OUTFALL SHOWING STREAM AND MILEAGE
- I - TYPE OF OUTFALL
- I - INDUSTRIAL SEWER
- W - STORM SEWER

ONTARIO WATER RESOURCES COMMISSION

### CITY OF OSHAWA OSHAWA CREEK Nº 4


SCALE: 1050 0 1050 FT.

DRAWN BY: L. L. BROOME

DATE: SEPTEMBER 1970

CHECKED BY: J.C.

DRAWING Nº: 70-151-DE



### LEGEND

0 - 6.98 - STREAM SAMPLING POINT SHOWING MILEAGE

0 - 5.58 - OUTFALL SHOWING STREAM AND MILEAGE  
W - TYPE OF OUTFALL

W - STORM SEWER


ONTARIO WATER RESOURCES COMMISSION

CITY OF OSHAWA  
OSHAWA CREEK  
No 5

SCALE: 1050 0 1050 FT.

DRAWN BY: L.L. BROOME DATE: SEPT, 1970

CHECKED BY: J. C. DRAWING No: 70-139-DE



# **LEGEND**

**0-6-08** - STREAM SAMPLING POINT SHOWING MILEAGE

**0-7-0** - OUTFALL SHOWING STREAM AND MILEAGE  
**W** - TYPE OF OUTFALL

W - STORM SEWER

ONTARIO WATER RESOURCES COMMISSION

CITY OF OSHAWA  
 OSHAWA CREEK  
 N° 6

SCALE : 1050 0 1050 FT.


DRAWN BY : L.L. BROOME

DATE : SEPT., 1970

CHECKED BY : J.C.

DRAWING N° : 70-140-DE





# **LEGEND**

- OE-7.9 - STREAM SAMPLING POINT SHOWING MILEAGE
- OE-7.9 - OUTFALL SHOWING STREAM AND MILEAGE
- W - TYPE OF OUTFALL
- W - STORM SEWER

ONTARIO WATER RESOURCES COMMISSION

CITY OF OSHAWA  
 OSHAWA CREEK (EAST BRANCH)  
 No 7

SCALE : 1050 0 1050 FT.	
DRAWN BY : L.L. BROOME	DATE : SEPT., 1970
CHECKED BY : J.C.	DRAWING No : 70-141-DE

APPENDIX V

City of Oshawa


Water Pollution Survey

1970

Maps

of

Goodman Creek



### LEGEND

OG-4.2 - STREAM SAMPLING POINT SHOWING MILEAGE

OG-4.0 - OUTFALL SHOWING STREAM AND MILEAGE

W - TYPE OF OUTFALL

W - STORM SEWER

ONTARIO WATER RESOURCES COMMISSION


CITY OF OSHAWA  
GOODMAN CREEK

Nº: 1

SCALE: 1050 0 1050 FT.

DRAWN BY: L.L. BROOME DATE: OCTOBER, 1970

CHECKED BY: J.C. DRAWING Nº: 70-167-DE



### LEGEND

OG-5.55 - STREAM SAMPLING POINT SHOWING MILEAGE

OG-5.54 - OUTFALL SHOWING STREAM AND MILEAGE  
D - TYPE OF OUTFALL

D - DRAINAGE DITCH

W - STORM SEWER

ONTARIO WATER RESOURCES COMMISSION


CITY OF OSHAWA  
GOODMAN CREEK  
Nº 2

SCALE : 1050 0 1050 FT.

DRAWN BY : L.L. BROOME DATE : OCTOBER 1970

CHECKED BY : J.C.

DRAWING Nº : 70-152-DE



# **LEGEND**

- OG-8-31 - STREAM SAMPLING POINT SHOWING MILEAGE
- OG-8-3(W) - OUTFALL SHOWING STREAM AND MILEAGE
- W - TYPE OF OUTFALL
- W - STORM SEWER

ONTARIO WATER RESOURCES COMMISSION

## CITY OF OSHAWA GOODMAN CREEK Nº 3

SCALE : 1050 0 1050 FT.

DRAWN BY : L. L. BROOME DATE : SEPT, 1970

CHECKED BY : J.C. DRAWING Nº 70-138-DE

APPENDIX VI

City of Oshawa


Water Pollution Survey

1970

Map

of

St. Julien Drain



# LEGEND

OS-0-5 - STREAM SAMPLING POINT SHOWING MILEAGE

OS-1-04 - OUTFALL SHOWING STEAM AND MILEAGE  
TYPE OUTFALL

W - STORM SEWER

ONTARIO WATER RESOURCES COMMISSION

CITY OF OSHAWA  
ST. JULIEN DRAIN

SCALE: 1050 0 1050 FT.

DRAWN BY: L.L.BROOME DATE: SEPTEMBER 1970

CHECKED BY: J.C. DRAWING NO: 70-149-DE

APPENDIX VII

City of Oshawa

Water Pollution Survey

1970


Maps

of

Harmony Creek

Includes: Main Branch  
Dean Avenue Drain  
West Branch  
Northwest Branch





# **LEGEND**

**H-1-1** - STREAM SAMPLING POINT SHOWING MILEAGE

**H-0-9** - OUTFALL SHOWING STREAM AND MILEAGE  
**T** - TYPE OF OUTFALL

**T** - TREATMENT PLANT EFFLUENT


ONTARIO WATER RESOURCES COMMISSION


CITY OF OSHAWA  
 HARMONY CREEK  
 (MAIN BRANCH)  
 N<sup>o</sup>: 1

SCALE: 1080 0 1050 FT.

DRAWN BY: L.L. BROOME DATE: SEPTEMBER 1970

CHECKED BY: J.C. DRAWING N<sup>o</sup>: 70-146-DE






### LEGEND

- H-2.88** - STREAM SAMPLING POINT SHOWING MILEAGE  
**H-4.08 D** - OUTFALL SHOWING STREAM AND MILEAGE  
           - TYPE OF OUTFALL  
           D - DRAINAGE DITCH  
           W - STORM SEWER

### ONTARIO WATER RESOURCES COMMISSION

### CITY OF OSHAWA HARMONY CREEK (MAIN BRANCH) No: 3

SCALE: 1050 0 1050 FT.	
DRAWN BY: L.L.BROOME	DATE: SEPTEMBER 1970
CHECKED BY: J.C.	DRAWING No: 70-144-DE



# **LEGEND**


- H-5-14 - STREAM SAMPLING POINT SHOWING MILEAGE
- H-4-7  
W - OUTFALL SHOWING STREAM AND MILEAGE  
- TYPE OF OUTFALL
- W - STORM SEWER

**ONTARIO WATER RESOURCES COMMISSION**

**CITY OF OSHAWA  
HARMONY CREEK  
(MAIN BRANCH)  
Nº: 4**

SCALE: 1050 0 1050 FT.	
DRAWN BY: L. L. BROOME	DATE: SEPT, 1970
CHECKED BY: J. C.	DRAWING Nº: 70-143-DE





# **LEGEND**

**HW-5-01** - STREAM SAMPLING POINT SHOWING MILEAGE

ONTARIO WATER RESOURCES COMMISSION

CITY OF OSHAWA  
HARMONY CREEK  
(WEST BRANCH)  
N<sup>o</sup> : 6


SCALE : 1050 0 1050 FT.

DRAWN BY : L. L. BROOME

DATE : SEPT., 1970

CHECKED BY : J. C.

DRAWING N<sup>o</sup> : 70-142-DE



# **LEGEND**

**HWO-5-62** — STREAM SAMPLING POINT SHOWING MILEAGE

**HWO-5-23** — OUTFALL SHOWING STREAM AND MILEAGE  
**W** — TYPE OF OUTFALL

W — STORM SEWER


ONTARIO WATER RESOURCES COMMISSION

CITY OF OSHAWA  
HARMONY CREEK  
(NORTHWEST BRANCH)  
Nº : 7

SCALE : 1050 0 1050 FT.

DRAWN BY : L.L. BROOME DATE : OCTOBER 1970

CHECKED BY : J.C. DRAWING Nº : 70-166-DE



### LEGEND

**HWO-6-38** - STREAM SAMPLING POINT SHOWING MILEAGE

**HWO-6-47** - OUTFALL SHOWING STREAM AND MILEAGE  
**W** - TYPE OF OUTFALL

**W** - STORM SEWER

ONTARIO WATER RESOURCES COMMISSION

CITY OF OSHAWA  
 HARMONY CREEK  
 (NORTHWEST BRANCH)  
 N<sup>o</sup> : 8

SCALE : 1080 0 1080 FT.

DRAWN BY : L. BROOME DATE : OCTOBER, 1970

CHECKED BY : J.C. DRAWING N<sup>o</sup> : 70-185-DE



APPENDIX VIII

City of Oshawa


Water Pollution Survey

1970

Map

of

Farewell Creek



# **LEGEND**

HF-1-01 - STREAM SAMPLING POINT SHOWING MILEAGE

HF-2-21 W - OUTFALL SHOWING STREAM AND MILEAGE  
W - TYPE OF OUTFALL

W - STORM SEWER

ONTARIO WATER RESOURCES COMMISSION

CITY OF OSHAWA  
FAREWELL CREEK

SCALE : 0 1080 FT.

DRAWN BY: L.L. BROOME

DATE: SEPTEMBER 1970


CHECKED BY: J.C.

DRAWING NO: 70-145-DE



Ontario  
Water Resources  
Commission

June  
1970



# **GUIDELINES AND CRITERIA**

FOR

## **WATER QUALITY MANAGEMENT IN ONTARIO**

BY THE

ONTARIO WATER RESOURCES COMMISSION

HON. G. A. KERR, Q.C.  
Minister

J. H. H. ROOT, M.P.P.  
Vice-Chairman

D. J. COLLINS,  
Chairman

135 St. Clair Avenue W., Toronto 7, Ontario  
June, 1970

## TABLE OF CONTENTS

	Page
INTRODUCTION .....	1
GUIDELINES FOR THE CONTROL OF WATER QUALITY .....	2
WATER QUALITY CRITERIA .....	3
—Zones of Passage and Mixing .....	3
—Statistical Problems in Setting Limits .....	3
—Category of Use	
1 Water Quality Criteria For Agricultural Uses (AGR) .....	4
2 Water Quality Criteria For The Protection of Fish, Other Aquatic Life and Wildlife (F & W) .....	8
3 Water Quality Criteria For Industrial Water Supplies (IWS) .....	15
4 Criteria For Public Water Supplies (PWS) .....	20
5 Criteria of Water Quality For Aesthetics and Recreation (A & R) .....	24
GLOSSARY OF TERMS .....	25
REFERENCES .....	26

# LIST OF TABLES

Table		Page
AGR-1	Water Quality Criteria for Agricultural Uses —Dairy Sanitation .....	4
AGR-2	Water Quality Criteria for Agricultural Uses —Livestock .....	5
AGR-3	Water Quality Criteria for Agricultural Uses —Irrigation .....	7
F & W-1	Water Quality Criteria for the Protection of Fish, Other Aquatic Life and Wildlife —Insecticides .....	11
F & W-2	Water Quality Criteria for the Protection of Fish, Other Aquatic Life and Wildlife —Herbicides, Fungicides, Defoliants, Algicides .....	13
IWS-1	Water Quality Criteria for Industrial Uses —Brewing and Soft Drinks .....	15
IWS-2	Water Quality Criteria for Industrial Uses —Chemical and Allied Products .....	15
IWS-3	Water Quality Criteria for Industrial Uses —Industrial Cooling .....	15
IWS-4	Water Quality Criteria for Industrial Uses —Food Processing .....	16
IWS-6	Water Quality Criteria for Industrial Uses —Iron and Steel .....	17
IWS-7	Water Quality Criteria for Industrial Uses —Petroleum .....	18
IWS-8	Water Quality Criteria for Industrial Uses —Pulp and Paper .....	18
IWS-9	Water Quality Criteria for Industrial Uses —Leather Tanning and Finishing .....	19
IWS-10	Water Quality Criteria for Industrial Uses —Textiles .....	19
PWS-1	Criteria for Public Water Supplies .....	21

## INTRODUCTION

In 1967, the Ontario Water Resources Commission announced its Policy Guidelines for Water Quality Control in the Province of Ontario. This publication contains a re-statement of the guidelines and introduces water quality criteria for various uses including public, agricultural and industrial water supply, recreation, aesthetic enjoyment and the propagation of fish and wildlife. The use of water for assimilation and dilution of treated wastes must take into consideration these many desirable uses. Application of the criteria to water uses within the drainage basins of the province, or parts thereof, will lead to the development of water quality standards for the control of water pollution.

## GUIDELINES FOR THE CONTROL OF WATER QUALITY

1 The water resources of Ontario must meet many needs, some of which are in conflict. The standards established, therefore, must be based on the best interests of the people of Ontario. These interests require the preservation, and restoration where necessary, of the quality of our water for the greatest number of uses. The use of water for the assimilation and dilution of treated waste effluents must take into consideration the variety of uses, including public, agricultural and industrial supply, recreation, aesthetic enjoyment and the propagation of fish and wildlife.

2 For each use of water there are certain water quality characteristics, identified as criteria, which should be met to ensure that the water is suitable for that use.

3 Water quality standards will be established by the Ontario Water Resources Commission for waters of drainage basins or parts thereof with important water uses, following consultation with agencies or persons having an interest or responsibility in the present or future use of the water in the basin for which the standards are to be established.

4 Water of a higher quality than that required by the standards will be maintained at that higher quality unless in the public interest an alteration of the quality is consistent with the protection of all uses which are in accordance with the water quality standards established.

There should be a constant effort to improve the quality of water, for it is recognized that the improvement of the quality of water makes it available for more uses.

5 Requirements for effluents and land drainage based on the applicable water quality standards, or criteria where such standards do not exist, will be established by the Commission in order to maintain acceptable water quality. More stringent methods of control and/or treatment of waste inputs and land drainage may become necessary as the use of water changes or increases, or as standards are re-defined.

6 In establishing effluent requirements from water quality standards a reserve capacity of the receiving water should be set aside to provide an adequate margin of protection in recognition of the limitations of water management theory and practice.

7 All wastes prior to discharge to any receiving watercourse must receive the best practicable treatment or control. Such treatment must be adequate to protect and wherever possible upgrade water quality in the face of population and industrial growth, urbanization and technological change.

8 Criteria and standards of water quality and effluent requirements will be defined quantitatively only where sound numerical information is available; otherwise, they will be described in appropriate detail. They will be re-defined from time to time in the light of new evidence.



## WATER QUALITY CRITERIA

The following criteria for water quality are a set of numerical and descriptive characteristics, carefully defined, and applicable to each major water use category such as agriculture; fish, other aquatic life and wildlife; industrial water supply; public water supply; recreation and aesthetics. The criteria are described for use in establishing Water Quality Standards for drainage basins which in turn will be used to determine Effluent Requirements for discharges of wastes and land drainage.

The responsibility for demonstrating that a waste effluent is harmless to water uses in the concentrations to be found in the receiving waters, rests with those producing the discharge. Zones of passage and/or mixing adjacent to outfalls at the limit of which water quality may be critical, will be prescribed by the Commission.

Reference is frequently made in the Criteria to the Report of the Committee on Water Quality, Federal Water Pollution Control Administration, U.S. Department of the Interior (1968). Acknowledgement of the report is gratefully given in recognition of its basic reference value.

### ZONES OF PASSAGE AND MIXING

Mixing zones in the vicinity of outfalls should be restricted as much as possible in extent and should provide for the safe passage of both fish and free-floating and drift organisms. Every precaution should be taken to ensure that at least two-thirds of the total cross-sectional area of a river or stream is characterized by a quality which is entirely favourable to the aquatic community at all times. In most cases this would preclude the use of a diffuser outfall which would distribute effluent uniformly across the river or stream. The water quality stand-

ard which defines the acceptable concentration of a substance contained in a waste discharge will apply at the periphery of the mixing zone or other specified sampling location.

Within mixing zones, it should be recognized that toxic wastes which will not evoke an avoidance response on the part of fish or other organisms should not be permitted. Where toxic materials are being discharged it should be assumed that the various components in the waste, regardless of the form in which they are present, may eventually be altered to the most toxic form in the aquatic environment. Adequate treatment of all wastes should be provided and mixing zones should not be considered as a substitute for proper treatment.

### STATISTICAL PROBLEMS IN SETTING LIMITS

The systematic surveillance of water and waste sources requires the collection of data to clearly represent the problems being studied. The problems are many and varied. In one case the average condition over a period of time may be required and the question arises over what period shall the average or median be taken; in another, the limit may be a figure that should not be exceeded at any time. If a standard for a certain constituent is "none", the question arises "how small an amount does this mean?" The answers vary with the type of standard and the circumstances governing the fluctuation of the indicator. In ground water problems, only the average over a considerable period of time is significant. Where required in the setting of standards and effluent requirements, definitions of limits will include the applicable sampling conditions, quantitative values and rates of discharge.

## 1 WATER QUALITY CRITERIA FOR AGRICULTURAL USES (AGR)

Agricultural production requires water of suitable quality for a variety of uses. Criteria for the major uses are given under three headings: Dairy Sanitation, Livestock Watering, and Irrigation.

Requirements for domestic and other farmstead uses and the common requirements for dairy sanitation are given elsewhere in the criteria for Private Water Supplies and Public Water Supplies.

### AGR-1 Dairy Sanitation

Modern methods for bulk handling of milk on farms require large volumes of good quality water to ensure a premium product. The quality of water needed for good dairy sanitation requires criteria for certain parameters that are additional to, or more stringent than, those required for private

water supplies. These are summarized under the headings "Permissible Criteria" and "Desirable Criteria". They should be used in conjunction with the criteria for public and private water supplies.

Treatment may prove satisfactory in meeting the criteria for certain of the inorganic chemicals such as iron and total hardness.

Waters that meet the desirable microbiological criteria can be used without disinfection; those meeting the permissible criteria require disinfection (chlorination), or chlorination and filtration, before use to reduce bacteria to levels where they will not cause deterioration of the quality of milk. Waters used for dairy sanitation should be sampled and tested at least monthly, in some cases daily, to ensure that they meet the microbiological criteria.

**TABLE AGR-1**  
**Water Quality Criteria for Agricultural Uses**  
**Dairy Sanitation**

Constituent or Characteristic	Permissible Criteria	Desirable Criteria
Inorganic Chemicals:		
Copper	0.1 mg/l	
Iron	0.1 mg/l	
pH (range)	6.8 to 8.5	
Potassium	20 mg/l	
Total hardness as CaCO <sub>3</sub>	150 mg/l	100 mg/l
Microbiological:		
Proteolytic and/or Lipolytic bacteria (20°C) (individual results)	500/100 ml	0/100 ml
Yeast		Absent
Mould		Absent
Physical:		Clear Colourless Good taste

### AGR-2 Livestock Watering

The health and productivity of livestock are affected by the quantities of various substances ingested as feed and as water. Accordingly, the amounts of certain substances that can be present without harm in water consumed by livestock will depend in part on the amounts of the same substances that are present in the feed in addition to a number of other factors which include: the daily water requirements and the species, age, and physiological condition of the animals, and the nature and quantities of other constituents of the feed and water.

Animals may be able to tolerate a fairly high level of total dissolved solids or bacteria if they are accustomed to such levels, but may be unable to tolerate a sudden change from waters with low dissolved solids or bacteria to waters with high dissolved solids or bacteria.

In addition to direct effects on the animals, certain substances may contaminate animal products

to the point where they will not be acceptable for human consumption.

The variability of the factors that influence the acceptability of water for livestock-watering purposes must be considered when using the water quality criteria. Although the criteria provide a general guide to the quality of water that will be acceptable for most livestock, there may be cases where water of different quality than that indicated by the criteria will be required or acceptable because of the nature, age, or condition of species being raised or because of special rearing conditions or feed components. In such cases, or where the quality of an individual supply is in doubt, the quality should be assessed in relation to the specific use.

Water meeting the permissible criteria will be satisfactory for most livestock under normal rearing conditions. Water meeting the desirable criteria should provide a palatable and safe source for all normal livestock-watering purposes.

TABLE AGR-2  
Water Quality Criteria for Agricultural Uses  
Livestock

Constituent or Characteristic	Permissible Criteria	Desirable Criteria
General Quality		ideally should meet the desirable criteria for private water supplies.
Inorganic Chemicals:		
Total Dissolved Solids	2500 mg/l	< 500 mg/l
Arsenic	0.05 mg/l	Absent
Cadmium	0.01 mg/l	Absent
Chromium (hexavalent)	0.05 mg/l	Absent
Fluoride	2.4 mg/l	1.2 mg/l
Lead	0.05 mg/l	Absent
Nitrate plus Nitrite (as N)	20 mg/l	< 10 mg/l
Selenium	0.01 mg/l	Absent
Sulphate	1000 mg/l	< 250 mg/l
Radioactivity:		
Radium-226	3 pc/l	< 1 pc/l
Strontium-90	10 pc/l	< 2 pc/l
Gross beta activity in the known absence of strontium-90 and alpha-emitting radionuclides.	1000 pc/l	< 100 pc/l
Microbiological: <sup>(1)</sup>		
Enterococci (35°C)	< 40/100 ml	0/100 ml
Algae	No heavy growth of blue-green algae	

(1) The supply should be free of barnyard runoff and of effluent contamination from either man or animals. The geometric mean of sample results should not exceed the values given.

### AGR-3 Irrigation

The suitability of water for irrigation cannot be defined precisely because the effects of the water on the crop being irrigated depend on many factors. These include: soil types, climatic conditions, irrigation practices, variations in the relation between the concentration and composition of the irrigation water and the soil solution, variations in the tolerance of different plants to the combined or individual constituents in the irrigation water or the soil solution, and the modifying effects of interrelations between and among the constituents. In general, for satisfactory irrigation, soils with poor drainage characteristics require water of higher quality than better drained soils.

In humid areas, excessive concentrations of salts or individual elements will normally be leached from the soil during periods of heavy rainfall or snowmelt before or after the growing season. This leaching action is another factor affecting the quality of water that can be used for irrigation. It may allow the use of water of poorer quality than that listed in these criteria for some crops and conditions without serious detrimental effects. Also through proper timing and adjustment of frequency and volumes of water applied, detrimental effects of poorer quality water may often be mitigated. Good drainage of soil may be a factor of similar importance as the quality of the water used.

The presence of sediment, pesticides, or pathogenic organisms in irrigation water, which may not specifically affect plant growth, may affect the acceptability of the product. Larger sediment particles could lead to plugging of sprinkler nozzles.

Although there are many variations in the quality of water that is suitable for specific irrigation uses, water quality criteria have been assembled as a guide to the quality of water that will meet many irrigation needs. The criteria are listed as permissible and desirable. Water meeting the desirable criteria should be satisfactory for irrigation of most crops in most soil types for long periods of time. Water meeting the permissible criteria, while suitable for many crops, soil and climatic conditions, could result in decreased yields for some crops if it is used repeatedly, unless there is dilution or leaching by precipitation or the application of excess irrigation water under favourable drainage conditions. Special crops or conditions, such as the growing of plants in greenhouses, may require irrigation with water of higher quality than that indicated by the desirable criteria.

The suitability of a given source of water for specific crops, soil types, and climatic conditions should be judged on an individual basis if its suitability has not been demonstrated by practice.

**TABLE AGR-3**  
**Water Quality Criteria for Agricultural Uses**  
**Irrigation**

Constituent or Characteristic	Permissible Criteria	Desirable Criteria
Physical:		
Temperature		55°F to 85°F
Microbiological: (1)		
Fecal Coliforms (44.5°C)	100/100 ml	0/100 ml
Enterococci (35°C)	20/100 ml	0/100 ml
Total bacteria (20°C)	100,000/100 ml	< 10,000/100 ml
Inorganic Chemicals:		
Aluminum	20.0 mg/l	< 1.0 mg/l
Arsenic	10.0 mg/l	< 1.0 mg/l
Beryllium	1.0 mg/l	< 0.5 mg/l
Boron	0.5 mg/l	0.3 mg/l
Cadmium	0.05 mg/l	< 0.005 mg/l
Chloride	150 mg/l	< 70 mg/l
Chloride—special requirement for tobacco	70 mg/l	< 20 mg/l
Chromium	20.0 mg/l	< 5.0 mg/l
Cobalt	10.0 mg/l	< 0.2 mg/l
Copper	5.0 mg/l	< 0.2 mg/l
Lead	20.0 mg/l	< 5.0 mg/l
Lithium	5.0 mg/l	< 5.0 mg/l
Manganese	20.0 mg/l	< 2.0 mg/l
Molybdenum	0.05 mg/l	< 0.005 mg/l
Nickel	2.0 mg/l	< 0.5 mg/l
pH (range)	4.8 to 9.0	
Residual Sodium Carbonate = $(\text{CO}_3^{--} + \text{HCO}_3^-) - (\text{Ca}^{++} + \text{Mg}^{++})$ expressed as mg eq/l	1.25 mg eq/l	< 1.25 mg eq/l
Selenium	0.05 mg/l	< 0.05 mg/l
Sodium Adsorption Ratio = $\frac{\text{Na}^+}{\frac{\text{Ca}^{++} + \text{Mg}^{++}}{2}}$ expressed as mg eq/l	6	< 4
Total dissolved solids		
Vanadium	500 mg/l	< 200 mg/l
Zinc	10.0 mg/l 5.0 mg/l	< 10.0 mg/l < 5.0 mg/l
Organic Chemicals:		
Pesticides	Insecticides, herbicides, fungicides, and rodenticides must not be present in waters used for irrigation in concentrations that are detrimental to crops, livestock, wildlife or man.	Absent

(1) The geometric mean of sample results should not exceed the values given.

## 2 WATER QUALITY CRITERIA FOR THE PROTECTION OF FISH, OTHER AQUATIC LIFE AND WILDLIFE (F & W)

The following criteria are considered to be satisfactory for fish, other aquatic life and wildlife. Reference is made to aspects of water quality considered to be most important in the light of current knowledge. Narrative guidelines are offered where quantification is not yet possible.

### Dissolved Materials

Dissolved materials should not be added to increase the concentration of dissolved solids by more than one-third of the natural condition of the receiving water, owing to potentially harmful osmotic effects of high concentrations. Dissolved materials that are harmful in relatively low concentrations are discussed in the section "Toxic Substances".

### pH, Alkalinity, Acidity

(1) pH should be maintained within a range of 6.5 to 8.5.

(2) To protect the carbonate system, and thus the productivity of the water, acid should not be added in sufficient quantity to lower the total alkalinity to less than 20 mg/l.

### Temperature

#### (1) General

Unless a special study shows that discharge of a heated effluent into the hypolimnion of a lake will be desirable, such practice is not recommended and water for cooling should not be pumped from the hypolimnion to be discharged to the same body of water.

The normal daily and seasonal temperature variations that were present before the addition of heat due to other than natural causes should be maintained.

Wherever possible, heated discharges should be located where elevated temperature will enhance public utilization of the water by supporting a wider variety of water uses.

#### (2) Great Lakes and Connecting Waters

(a) Heated discharges are not permitted that may stimulate production of nuisance organisms or vegetation or that are or may become injurious to wildlife, waterfowl, fish or other aquatic life or the growth and reproduction thereof. For each discharge of a heated effluent, acceptable mixing zones will be established on the basis of features and facts pertinent to that specific situation.

(b) Heat may not be discharged in the vicinity of spawning areas or where increased water tem-

perature might interfere with recognized movements of spawning or migrating fish populations.

### (3) Inland Waters

(a) Heated discharges to inland waters will not be permitted unless it is clearly demonstrated that heated effluents will enhance the usefulness of the water resource without endangering the production and optimum maintenance of wildlife, fish and other aquatic species. It shall be the responsibility of the user to provide evidence to support the acceptability of the discharge under these terms.

(b) Inland trout streams, salmon streams, trout and salmon lakes and the hypolimnion of lakes and reservoirs containing salmonids and other cold water forms should not be warmed.

(c) Heat may not be discharged in the vicinity of spawning areas or where increased temperature might interfere with recognized movements of spawning or migrating fish populations.

### Dissolved Oxygen

#### (1) Warm-water Biota

The dissolved oxygen (DO) concentration should be above 5 mg/l at all times, except that in certain situations concentrations may range between 5 and 4 mg/l for short intervals within any 24-hour period provided that water quality is favourable in all other respects.

#### (2) Cold-water Biota

In spawning areas, DO levels must not be below 7 mg/l at any time. Elsewhere, DO concentrations should not be below 6 mg/l. In certain situations, they may range between 6 and 5 mg/l for short intervals within any 24-hour period, provided the water quality is favourable in all other respects.

### Carbon Dioxide

The 'free' carbon dioxide concentration should not exceed 25 mg/l.

### Oil

Oil, petrochemicals or other immiscible substances that will cause visible films or toxic, noxious or nuisance conditions should not be added to water.

### Turbidity

(1) Turbidity associated with waste inputs should not exceed 50 Jackson units in warm-water streams or 10 Jackson units in cold-water streams.

(2) There should be no discharge which would cause turbidities exceeding 25 Jackson units in warm-water lakes or 10 Jackson units in cold-water or oligotrophic lakes.

### Settleable Materials

Substances should not be added that will adversely affect the aquatic biota or will create objectionable deposits on the bottom or shore of any body of water.

### Colour and Transparency

For effective photosynthetic production of oxygen, it is required that 10 per cent of the incident light reach the bottom of any desired photosynthetic zone in which adequate dissolved oxygen concentrations are to be maintained.

### Floating Materials

All floating materials, other than those of natural origin, should be excluded from streams and lakes.

### Tainting substances

All materials that will impart odour or taste to fish or edible invertebrates should be excluded from receiving waters at levels that produce tainting.

### Radionuclides

Radioactive materials should not be present in natural waters as a consequence of failure to exercise necessary controls of radioactivity releases to keep exposure to a minimum.

Experience has shown that standards established for drinking water assure that people will receive no more than currently acceptable amounts of radioactive materials from aquatic sources and that fish and other aquatic life will not receive an injurious dose of radiation.

Thus, present standards accepted for the protection of fish and other aquatic life are as follows:

	pc/l
Gross beta emitters	1000
Radium-226	3
Strontium-90	10

Where other radioisotopes occur, the significance of the exposure of aquatic species to these forms of radiation should be assessed for each situation, both with respect to potential damage to the organisms themselves and to humans where fish or other edible forms are utilized.

### Plant Nutrients and Nuisance Growths

(1) Nutrients from unnatural sources that will stimulate production of algae, nuisance vegetation or offensive slime growths should not be added to water. The addition of sulphates or manganese oxide to a lake should be limited if iron is present in the hypolimnion as these substances may increase the quantity of available phosphorus.

(2) Organic or other materials that will promote an increased zone of anaerobic decomposition within a lake, reservoir or other body of water should not be allowed to enter the water.

(3) The naturally-occurring ratios of nitrogen (particularly  $\text{NO}_3$  and  $\text{NH}_4$ ) to total phosphorus, and their amounts, should not be radically changed by the addition of materials from waste sources and land drainage.

### Toxic Substances

Toxic substances must not be added to water in concentrations or combinations that are toxic or harmful to human, animal, plant or aquatic life, except where the application of approved substances for the control of nuisance organisms has been authorized by the Commission (Section 28b, OWRC Act).

The evaluation of toxicity for aquatic organisms is based on use of the TLM or median tolerance limit. This represents the concentration at which half the test organisms will succumb over a given period of exposure such as 24, 48 or 96 hours. It does not, therefore, represent the safe concentration and an application factor is applied to ensure a safe condition, including allowance for sub-lethal effects.

#### (1) Substances of Unknown Toxicity

All effluents containing foreign materials should be considered harmful and not permissible until bioassay tests have shown otherwise. The onus for demonstrating that an effluent is harmless in the concentrations to be found in the receiving waters rests with those responsible for the discharge. Information concerning acceptable bioassay procedures is available from the Commission.

#### (2) Application Factors

Concentration of materials that are non-persistent (that is, have a half-life of less than 96 hours), or have non-cumulative effects after mixing with the receiving waters, should not exceed 1/10 of the applicable 96-hour TLM value at any time or place based on species representative of local conditions. The 24-hour average of the concentration of these materials should not exceed 1/20 of the TLM value after mixing. For other toxicants, the concentrations should not exceed 1/20 and 1/100 of the TLM value under the aforementioned conditions.

#### (3) Additive Effects

When two or more toxic materials that have additive effects are present at the same time in the receiving water, some reduction is necessary in the permissible concentrations as derived from bioassays on individual substances or wastes. The amount of reduction required is a function of both the number of toxic materials present and their concentrations in respect to the derived permissible concentration. An appropriate means of assuring that the combined

amounts of the several substances do not exceed a permissible concentration for the mixture is through the use of the following relationship:

$$\left( \frac{C_a}{L_a} + \frac{C_b}{L_b} + \dots + \frac{C_n}{L_n} \leq 1 \right)$$

where  $C_a, C_b, \dots, C_n$  are the measured concentrations of the several toxic materials in the water and  $L_a, L_b, \dots, L_n$  are the respective permissible concentration limits derived for the materials on an individual basis. Should the sum of the several fractions exceed one, then a local restriction on the concentration of one or more of the substances is necessary.

#### (4) Pesticides

##### (a) Chlorinated Hydrocarbons:

Any addition of chlorinated hydrocarbon insecticides is likely to cause damage to some desired organisms and their use should be avoided.

##### (b) Other Chemical Pesticides:

Other pesticides and herbicides gaining access to water can cause damage to desirable organisms and should be used with utmost discretion and caution. Tables F & W-1 and F & W-2 list the 48-hour TLM values of a number of pesticides for various types of fresh water organisms. To provide reasonably safe concentrations of these materials in receiving waters, application factors ranging from 1/10 to 1/100 should be used, with these values depending on the characteristic of the pesticide in question and used as specified in (2) above. Concentrations thus derived may be considered tentatively safe under the conditions specified. TLM values and related application factors are subject to revision as additional bioassay information is obtained for species which may be more representative of local conditions.

#### (5) Other Toxic Substances

- (a) ABS: The concentration of ABS should not exceed 1/7 of the 48-hour TLM at any time or place.
- (b) LAS: The concentration of LAS should not exceed 1/7 of the 48-hour TLM at any time or place.
- (c) ARSENIC: An application factor of 1/100 should be applied to the 96-hour TLM value as a tentative safe concentration for continuous exposure. An environmen-

tal level of .01 mg/l should not be exceeded under any circumstances.

- (d) AMMONIA: Permissible concentrations of ammonia should be determined by the flow-through bioassay with the pH of the test solution maintained at 8.5, DO concentrations between 4 and 5 mg/l, and temperatures near the upper allowable levels.
- (e) CADMIUM: The concentration of cadmium must not exceed 1/500 of the 96-hour TLM concentration at any time or place.
- (f) CHROMIUM: The concentration of chromium should not exceed 1/100 of the 96-hour TLM at any time or place.
- (g) COPPER: The maximum copper (expressed as Cu) concentration at any time or place shall not be greater than 1/12 of the 96-hour TLM value. The maximum permissible concentration for continuous exposure is between 3 per cent and 7 per cent of the 96-hour TLM.
- (h) LEAD: The concentration of lead should not exceed 1/20 of the 96-hour TLM at any time or place and the 24-hour average should not exceed 1/100 of the 96-hour TLM concentration after mixing.
- (i) MERCURY: Owing to demonstrated cumulative effects of mercury in fish, and the attendant hazard to other animals, discharges of mercury to water should be avoided.
- (j) NICKEL: The concentration of nickel should not exceed 1/50 of the 96-hour TLM concentration at any time or place.
- (k) ZINC: The concentration of zinc should not exceed 1/100 of the 96-hour TLM concentration at any time or place.



TABLE F &amp; W-1 INSECTICIDES\*

(48-hour TLm values from static bioassay, in micrograms per litre. Exceptions are noted.)

Pesticide	Stream Invertebrate <sup>1</sup>		Cladocerans <sup>2</sup>		Fish <sup>3</sup>		Gammarus Lacustris, <sup>4</sup> TLm
	Species	TLm	Species	TLm	Species	TLm	
Abate	Pteronarcys californica	100			Brook trout	1,500	640
Aldrin <sup>5</sup>	P. californica	8	Daphnia pulex	28	Rainbow trout	3	12,000
Allethrin	P. californica	28	D. pulex	21	- do -	19	20
Azodrin					- do -	7,000	
Aramite			D. magna	345	Bluegill	35	100
Baygon <sup>5</sup>	P. californica	110			Fathead	25	50
Baytex <sup>5</sup>	P. californica	130	Simocephalus serrulatus	3.1	Brown t.	80	70
Benzene hexachloride (lindane)	P. californica	8	D. pulex	460	Rainbow t.	18	88
Bidrin	P. californica	1900	D. pulex	600	- do -	8,000	790
Carbaryl (sevin)	P. californica	1.3	D. pulex	6.4	Brown t.	1,500	22
Carbophenothion (trithion)			D. magna	0.009	Bluegill	225	28
Chlordane <sup>6</sup>	P. californica	55	S. serrulatus	20	Rainbow t.	10	80
Chlorobenzilate			S. serrulatus	550	- do -	710	
Chlorthion			D. magna	4.5			
Coumaphos			D. magna	1			0.14
Cryolite			D. pulex	5,000	Rainbow t.	47,000	
Cyflethrin			D. magna	55			
DDD (TDE) <sup>5</sup>	P. californica	1100	D. pulex	3.2	Rainbow t.	9	1.8
DDT <sup>5</sup>	P. californica	19	D. pulex	0.36	Bass	2.1	2.1
Delnav (dioxathion)					Bluegill	14	690
Delmeton (systex)				14	- do -	81	
Diazinon <sup>5</sup>	P. californica	60	D. pulex	0.9	- do -	30	500
Dibrom (naled)	P. californica	16	D. pulex	3.5	Brook t.	78	160
Dieldrin <sup>5</sup>	P. californica	1.3	D. pulex	240	Bluegill	3.4	1,000
Dilan			D. magna	21	- do -	16	600
Dimethoate (cygon)	P. californica	140	D. magna	2500	- do -	9600	400
Dimethrin					Rainbow t.	700	
Dichlorvos <sup>5</sup> (DDVP)	P. californica	10	D. pulex	0.07	Bluegill	700	1
Disulfotol (di-syston)	P. californica	18			- do -	40	70

\* From Report of the Committee on Water Quality Criteria, Federal Water Pollution Control Administration, U.S. Department of the Interior (1968).

TABLE F &amp; W-1—continued

Pesticide	Stream Invertebrate <sup>1</sup>		Cladocerans <sup>2</sup>		Fish <sup>3</sup>		Gammarus Lacustris, <sup>4</sup> TLm
	Species	TLm	Species	TLm	Species	TLm	
Dursban	Peteronareella badia	1.8			Rainbow t.	20	0.4
Endosulfan (thiodan)	P. californica	5.6	D. magna	240	- do -	1.2	64
Endrin <sup>5</sup>	P. californica	0.8	D. pulex	20	Bluegill	0.2	4.7
EPH			D. magna	0.1	- do -	17	36
Ethion	P. californica	14	D. magna	0.01	- do -	230	3.2
Ethyl guthion <sup>5</sup>			D. pulex		Rainbow t.		
Fenthion	P. californica	39	D. pulex	4			
Guthion <sup>5</sup>	P. californica	8	D. magna	0.2	Rainbow t.	10	0.3
Heptachlor <sup>5</sup>	P. badia	4	D. pulex	42	- do -	9	100
Kelthane (dicofel)	P. californica	3000	D. magna	390	- do -	100	
Kepone					- do -	37.5	
Malathion <sup>5</sup>	P. badia	6	D. pulex	1.8	Brook t.	19.5	1.8
Methoxychlor <sup>5</sup>	P. californica	8	D. pulex	0.8	Rainbow t.	7.2	1.3
Methyl parathion <sup>5</sup>			D. magna	4.8	Bluegill	8000	
Morestan	P. californica	40			- do -	96	
Ovex	P. californica	1500			- do -	700	
Paradichlorobenzene					Rainbow t.	880	
Parathion <sup>5</sup>	P. californica	11	D. pulex	0.4	Bluegill	47	6
Perthane			D. magna	9.4	Rainbow t.	7	
Phosdrin <sup>5</sup>	P. californica	9	D. pulex	0.16	- do -	17	310
Phosphamidon	P. californica	460	D. magna	4	- do -	8000	3.8
Pyrethrins	P. californica	64	D. pulex	25	- do -	54	18
Rotenone	P. californica	900	D. pulex	10	Bluegill	22	350
Strobane <sup>5</sup>	P. californica	7			Rainbow t.	2.5	
Tetradifon (tedion)					Bluegill	1100	140
TEPP <sup>5</sup>					Fathead	390	52
Thanite			D. magna	450			
Thimet					Bluegill	5.5	70
Toxaphene <sup>5</sup>	P. californica	7	D. pulex	15	Rainbow t.	2.8	70
Trichlorofon	P. badia	22	D. magna	8.1	- do -	160	60
(diptere) <sup>5</sup>							
Zectran	P. californica	16	D. pulex	10	- do -	8000	76

TABLE F &amp; W-2

## HERBICIDES, FUNGICIDES, DEFOLIANTS, ALGICIDES\*

Pesticide	Stream Invertebrate <sup>1</sup>		Cladocerans <sup>2</sup>		Fish <sup>3</sup>		Gammarus lacustris, <sup>4</sup> TLm
	Species	TLm	Species	TLm	Species	TLm	
Ametryne					Rainbow t.	3400	
Aminotriazole					Bluegill	257	
Aquathol			Daphnia magna	3600	Rainbow t.	12,600	
Atrazine					Bluegill	1400	10,000
Azide, potassium					- do -	980	9000
Azide, sodium					- do -	1100	
Copper chloride					- do -	150	
Copper sulphate					- do -	20,000	1500
Dichlobenil	Pteronarcys californica	44,000	Daphnia pulex	3700			
2,4-D PGBEE			D. pulex	3200	Rainbow t.	960	1800
2,4-D BEE	P. californica	1800			Bluegill	2100	760
2,4-D isopropyl					- do -	800	
2,4-D butyl ester					- do -	1300	
2,4-D butyl + isopropyl ester					- do -	1500	
2,4,5-T isooctyl ester					- do -	16,700	
2,4,5-T isopropyl ester					- do -	1700	
2,4,5-T PCBE					- do -	560	
2(2,4-DP) BEE					- do -	1100	
Dalapon	P. californica		D. magna	6000			
	Very low toxicity					Very Low Toxicity	
Dead-X	P. californica	5000	D. pulex	3700	Rainbow t.	9400	5600
DEF	P. californica	2300			Bluegill	36	230
Dexon	P. californica	42,000			Bluegill	23,000	6000
Dicamba					non-toxic		5800
Dichlone			D. magna	26	Rainbow t.	48	11,500
Difolitan	P. californica	150			Channel Cat	31	6500
Dinitroresol	P. californica	560			Rainbow t.	210	
Diquat					Rainbow t.	12,300	
Diuron	P. californica	2800	D. pulex	1400	- do -	4300	380
Du-ter					Bluegill	33	
Dyrene			D. magna	490		15	
Endothal, copper					Rainbow t.	290	

\* From Report of the Committee on Water Quality Criteria, Federal Water Pollution Control Administration, U.S. Department of the Interior (1968).

TABLE F &amp; W-2—continued

Pesticide	Stream Invertebrate <sup>1</sup>		Cladocerans <sup>2</sup>		Fish <sup>3</sup>		Gammarus lacustris, <sup>4</sup> TLm
	Species	TLm	Species	TLm	Species	TLm	
Endothal dimethylamine					Rainbow t.	1150	
Fenac, acid	P. californica	70,000			- do -	16,500	
Fenac, sodium	P. californica	80,000	D. pulex	4500	- do -	7500	18,000
Hydram (molinat)	P. californica	3500			- do -	290	
Hydrothol 191					- do -	690	1000
Lanstan (Korax)					- do -	100	5500
LFN					- do -	79	
Paraquat	P. californica		D. pulex	3700	Very low toxicity		18,000
	Very low toxicity				Rainbow t.	7800	
Propazine					- do -	650	
Silvex, PGBEE			D. pulex	2000	Bluegill	1400	
Silvex, isoctyl					- do -	1200	
Silvex, BEE					Rainbow t.	5000	21,000
Simazine	P. californica	50,000			- do -	36,500	
Sodium arsenite	P. californica		Simocephalus serrulatus	1400			
	Very low toxicity				- do -	2500	48,000
Tordon (picloram)					- do -	11	5600
Trifluralin	P. californica	4200	D. pulex	240	- do -	5900	25,000
Vernam <sup>5</sup> (vernolate)							

1 Stonefly bioassay was done at Denver, Colo., and at Salt Lake City, Utah. Denver tests were in soft water (35 mg/l TDS), non-aerated, 60 F. Salt Lake City tests were in hard water (150 mg/l TDS), aerated, 48-50 F. Response was death.

2 Daphnia pulex and Simocephalus serrulatus bioassay was done at Denver, Colo., in soft water (35 mg/l TDS), non-aerated, 60 F. Daphnia magna bioassay was done at Pennsylvania State University in hard water (146 mg/l TDS), non-aerated, 68 F. Response was immobilization.

3 Fish bioassay was done at Denver, Colo., and at Rome N.Y. Denver tests were with 2-inch fish in soft water (35 mg/l TDS), non-aerated, trout at 55 F.; other species at 65 F. Rome tests were with 2-2 1/2 inch fish in soft water (6 mg/l TA: pH 5.85-6.4), 60 F. Response was death.

4 Gammarus bioassay was done at Denver, Colo., in soft water (35 mg/l TDS), non-aerated, 60 F. Response was death.

5 Becomes bound to soil when used according to directions, but highly toxic (reflected in numbers) when added directly to water.

### 3 WATER QUALITY CRITERIA FOR INDUSTRIAL WATER SUPPLIES (IWS)

Desired water quality criteria are tabled for the major industrial classifications as follows:

Brewing and Soft Drinks	— IWS-1
Chemical and Allied Products	— IWS-2
Industrial Cooling	— IWS-3
Food Processing	— IWS-4
Electroplating and Metal Finishing	— IWS-5
Iron and Steel	— IWS-6
Petroleum	— IWS-7
Pulp and Paper	— IWS-8
Leather Tanning and Finishing	— IWS-9
Textiles	— IWS-10

While the values listed should not normally be exceeded, these water quality criteria can vary considerably for the same industrial process depending on factors such as the technological age of plant design.

A raw surface water and/or ground water supply which is used by many different industries may not satisfy the widely varying criteria for each use. However, water treatment technology in its present state of development permits the utilization of surface water of literally any available quality to produce water of any desired quality at the point of use in industry.

Most industries located on municipal water supply systems find the quality of water provided to be satisfactory. If the water quality requirements of an industry are such that water of higher quality than that provided by the municipality is required for specific process use, the industry generally accepts the additional costs involved to produce the higher quality water.

TABLE IWS-1

#### WATER QUALITY CRITERIA FOR THE BREWING AND SOFT DRINK INDUSTRIES

(Unless otherwise indicated, units are mg/l)

Characteristic	Concentration
Alkalinity (CaCO <sub>3</sub> )	85
pH, units	(1)
Hardness (CaCO <sub>3</sub> )	(1)
Chloride (Cl)	250 <sup>(2)</sup>
Sulphate (SO <sub>4</sub> )	250 <sup>(2)</sup>
Iron (Fe)	0.3 <sup>(3)</sup>
Manganese (Mn)	0.05
Fluoride (F)	1 <sup>(3)</sup>
Dissolved solids	(1)
Organics: carbon chloroform extract (CCE)	0.15 <sup>(3)</sup>
Coliform bacteria, count/100 ml	(3)
Colour, units	5 <sup>(4)</sup>

Taste, threshold number  
Odour, threshold number

(4, 5)

(4, 5)

- (1) Controlled by treatment for other constituents.
- (2) For brewing, value should not exceed 100 mg/l.
- (3) Not greater than OWRC Drinking Water Objectives.
- (4) In general, public water supplies are given conventional treatment such as coagulation, filtration and chlorination. Any additional requirement for higher quality, for example, deionized water, is the responsibility of the industry. To ensure low organic content, activated carbon treatment is used by industry.
- (5) Zero, not detectable by test.

TABLE IWS-2

#### WATER QUALITY CRITERIA FOR THE CHEMICAL AND ALLIED PRODUCTS INDUSTRIES\*

(Unless otherwise indicated, units are mg/l)

Characteristic	Concentration <sup>1</sup>
Alkalinity (as CaCO <sub>3</sub> )	150
Iron (Fe)	0.3
Manganese (Mn)	0.1
Calcium (Ca)	50
Magnesium (Mg)	25
Bicarbonate (HCO <sub>3</sub> )	250
Sulphate (SO <sub>4</sub> )	250
Chloride (Cl)	250
Nitrate (NO <sub>3</sub> ) as N	10
Hardness (as CaCO <sub>3</sub> )	250
pH, units	6.5-8.5
Dissolved solids	750
Silica	50
Colour, units	20
Suspended solids	15

\* Industries include the manufacture of synthetic rubber, plastics, fertilizers, soap and detergents, organic and inorganic chemicals, etc.

- (1) Because of the varying requirements of the many uses in the vast number of chemical industries, more stringent restrictions are placed on several of the above noted characteristics. In some cases, any concentration can be handled, while in others, the raw water is accepted as received provided it meets total solids or other limiting values. The above concentrations are suggested guidelines that should be suitable for the majority of uses in the chemical industry.

TABLE IWS-3

#### WATER QUALITY CRITERIA FOR COOLING WATER\*

(Unless otherwise indicated, units are mg/l)

Characteristic	Concentration
Turbidity	50
Hardness	50
Iron	0.5
Manganese	0.5

- \* Cooling waters should have appropriate initial temperatures and should not deposit scale, be corrosive or encourage the growth of slimes. Among the constituents of natural water that may prove detrimental to its use for cooling purposes are hardness, suspended solids, dissolved gases, acids, oil and other organic compounds and slime-forming organisms.

TABLE IWS-4

# WATER QUALITY CRITERIA FOR THE FOOD PROCESSING INDUSTRY

(Unless otherwise indicated, units are mg/l)

Characteristic	Concentration
Alkalinity (CaCO <sub>3</sub> )	150
pH, units	6.5-8.5
Hardness (CaCO <sub>3</sub> )	150
Chloride (Cl)	250
Sulphate (SO <sub>4</sub> )	250
Iron (Fe)	0.2
Manganese (Mn)	0.2
Chlorine (Cl)	(1)
Fluoride (F)	(1)(2)
Silica (SiO <sub>2</sub> )	50
Phenol	(3, 4)
Nitrate (NO <sub>3</sub> ) as N	10 <sup>(2)</sup>
Nitrite (NO <sub>2</sub> ) as N	(3)
Organics:	
Carbon chloroform extract (CCE)	0.15
Odour, threshold number	(3)
Taste, threshold number	(3)
Turbidity	(4)
Colour, units	5
Dissolved solids	500
Suspended solids	10
Coliform, count/100 ml	(4)
Total bacteria, count/100 ml	(7)

- (1) Process waters for food canning are purposely chlorinated to a selected, uniform level. An unchlorinated supply must be available for preparation of canning syrups.
- (2) Waters used in the processing and formulation of foods for babies should be low in fluorides concentration. Also, because high nitrate intake is alleged to be involved in infant illnesses, the concentration of nitrates in waters used for processing baby foods should be low.
- (3) Zero, not detectable by test.
- (4) Because chlorination of food processing waters is a desirable and widespread practice, the phenol content of intake waters must be considered. Phenol and chlorine in water can react to form chlorophenol, which even in trace amounts can impart a medicinal off-flavour to foods.
- (5) Maximum permissible concentration may be lower depending on type of substance and its effect on odour and taste.
- (6) As required by OWRC Drinking Water Objectives.
- (7) The total bacterial count must be considered as a quality requirement for waters used in certain food processing operations. Other than aesthetic considerations, high bacterial concentration in waters coming in contact with frozen foods may significantly increase the count per gram for the food. Waters used to cool heat-sterilized

cans or jars of food must be low in total count for bacteria to prevent serious spoilage due to aspiration of organisms through container seams. Chlorination is widely practised to assure low bacterial counts on container cooling waters.

## WATER QUALITY CRITERIA FOR THE ELECTRO- PLATING AND METAL FINISHING INDUSTRIES — IWS-5

Plating-room processes that utilize water include the stripping or pickling operations, cleaning by organic solvents or alkaline solutions, rinsing, and electrochemical plating. For acid stripping or for alkaline cleaning, the quality of water used in the baths is seldom critical, for the added chemicals far outweigh the natural constituents of the water. Hardness of water may be detrimental when soaps or alkaline cleaning agents are used.

For rinsing and for plating, water quality is frequently a major problem. High quality water is of primary importance to assure satisfactory finished work. For decorative plating, water spots and stains may necessitate reworking, wiping, buffing, and other laborious operations. Before the application of any organic corrosion-resistant coating, it is almost a necessity to use demineralized water in the final rinse, in order to achieve adhesion of the coating. A high concentration of dissolved solids is especially detrimental in rinse waters.

In plating baths, iron, aluminum, calcium, magnesium, sodium, potassium, carbonate, bicarbonate, sulphide, sulphite, sulphate, fluoride, chloride, silicate, copper, and lead have been reported to cause difficulties under certain conditions. Considerable evaporation occurs from plating baths and hence the ions present in the make-up water are concentrated to the extent that they are troublesome.

Calcium and magnesium are especially troublesome in plating baths, for they tend to precipitate to form scale on the heated surface or a sludge in the water. There is a probability of these precipitates being included in the electro-deposit, causing pits, porosity, and roughness. Magnesium may also reduce the "throwing power" in chromium baths, but on the other hand, magnesium sulphate is sometimes added to nickel-plating baths to produce softer deposits, to minimize certain types of pitting, and to increase throwing power.

Sodium and potassium are generally not harmful in plating operations, although sodium may cause brittle deposits in nickel baths or reduce the throwing power in chromium solutions. Iron is one of the most troublesome pollutants of many plating operations. In a nickel-sulphate bath, it may cause hazy, streaked, pitted, or brittle deposits; in acid copper solutions, it produces rough deposits; in chromium baths, it reduces the throwing power; in

cadmium cyanide, it causes hazy deposits; in silver cyanide, stained deposits; and in zinc sulphate baths it lowers the plating efficiency and the protective value of the coating.

Among the anions, bicarbonates are detrimental in heated alkaline baths, for they tend to be converted to carbonates and accelerate the precipitation of calcium. Moreover, they buffer the water and require higher dosages of acid or alkali to obtain

the desired pH value. Chlorides have been reported to cause rough, modular, iridescent, and crystalline deposits in cadmium, copper, silver, and tin baths respectively. Organic substances reduce chromium, and cause rough, hazy, streaked, coloured, or pitted deposits under various conditions. Colour and turbidity are similarly objectionable.

Abstracted from "Water Quality Criteria", 2nd Edition, State Water Quality Control Board, California, Publication No. 3-A

**TABLE IWS-6**  
**WATER QUALITY CRITERIA FOR THE**  
**IRON AND STEEL INDUSTRY**

(Unless otherwise indicated, units are mg/l)

Characteristic	Quenching, hot rolling, gas cleaning	Cold rolling	Selected rinse waters	
			Softened	Demineralized
Suspended solids	25	10	(2)	(2)
Dissolved solids	(1)	(1)	(1)	(2)
Alkalinity (CaCO <sub>3</sub> )	(3)	(3)	(3)	(2)
Hardness (CaCO <sub>3</sub> )	(3)	(3)	100	(2)
pH, units	6.0-9.0	6.0-9.0	6.0-9.0	(3)
Chloride (Cl)	150	150	150	(2)
Dissolved oxygen (O <sub>2</sub> )	(4)	(4)	(4)	(4)
Temperature, °F	100	100	100	100
Oil	(1)	(2)	(2)	(2)
Floating material	(1)	(2)	(2)	(2)

(1) Accepted as received if meeting total solids or other limiting values.

(2) Zero, not detectable by test.

(3) Controlled by treatment for other constituents.

(4) Minimum to maintain aerobic conditions.

TABLE IWS-7

**WATER QUALITY CRITERIA FOR THE  
PETROLEUM INDUSTRY**

(Unless otherwise indicated, units are mg/l)

Characteristic	Concentration
Silica (SiO <sub>2</sub> )	(1)
Iron (Fe)	1
Calcium (Ca)	75
Magnesium (Mg)	25
Bicarbonate (HCO <sub>3</sub> )	(1)
Sulphate (SO <sub>4</sub> )	(1)
Chloride (Cl)	200
Fluoride (F)	(1)
Nitrate (NO <sub>3</sub> ) as N	(1)
Dissolved solids	750
Suspended solids	10
Hardness (CaCO <sub>3</sub> )	350
Noncarbonate hardness (CaCO <sub>3</sub> )	70
Colour, units	(1)
pH, units	6.0-9.0

(1) Accepted as received if meeting total solids or other limiting values.

TABLE IWS-8

**WATER QUALITY CRITERIA FOR THE  
PULP AND PAPER INDUSTRY**

(Unless otherwise indicated, units are mg/l)

Characteristic	Mechanical Pulping	Chemical Pulp and Paper	
		Unbleached	Bleached
Silica (SiO <sub>2</sub> )	(1)	50	50
Aluminum (Al)	(1)	(1)	(1)
Iron (Fe)	0.3	1.0	0.1
Manganese (Mn)	0.1	0.1	0.05
Zinc (Zn)	(1)	(1)	(1)
Calcium (Ca)	(1)	20	20
Magnesium (Mg)	(1)	10	10
Sulphate (SO <sub>4</sub> )	(1)	(1)	(1)
Chloride (Cl)	500	200	200
Dissolved solids	(1)	(1)	(1)
Suspended solids	(1)	10 <sup>(2)</sup>	10 <sup>(2)</sup>
Hardness (CaCO <sub>3</sub> )	(1)	100	100
pH, units	6.0-9.0	6.0-9.0	6.0-9.0
Colour, units	30	30	10
Temperature, °F	(1)	(1)	95

(1) Accepted as received if meeting total solids or other limiting values.

(2) No gritty or colour-producing solids.



TABLE IWS-9

**WATER QUALITY CRITERIA FOR THE  
LEATHER TANNING AND FINISHING INDUSTRY**

(Unless otherwise indicated, units are mg/l)

Characteristic	Tanning Processes	General Finishing Processes	Colouring
Alkalinity (CaCO <sub>3</sub> )	(1)	130	130
pH, units	6.0-8.0	6.0-8.0	6.0-8.0
Hardness (CaCO <sub>3</sub> )	150	(2)	(3, 4)
Calcium (Ca)	60	(2)	(3, 4)
Chloride (Cl)	250	250	(5)
Sulphate (SO <sub>4</sub> )	250	250	(5)
Iron (Fe)	0.3	0.3	0.1
Manganese (Mn)	0.2	0.2	0.01
Organics:			
Carbon chloroform extract (CCE)	(5)	0.2	(3)
Colour, units	5	5	5
Coliform bacteria, count/100 ml	(6)	(6)	(5)
Turbidity	(3)	(3)	(3)

(1) Accepted as received if meeting total solids or other limiting values.

(2) Lime softened.

(3) Zero, not detectable by test.

(4) Demineralized or distilled water.

(5) Concentration not known.

(6) OWRC Drinking Water Objectives.

TABLE IWS-10

**WATER QUALITY CRITERIA FOR THE  
TEXTILE INDUSTRY**

(Unless otherwise indicated, units are mg/l)

Characteristic	Sizing Suspension	Scouring	Bleaching	Dyeing
Iron (Fe)	0.3	0.1	0.1	0.1
Manganese (Mn)	0.05	0.01	0.01	0.01
Copper (Cu)	0.05	0.01	0.01	0.01
Dissolved solids	100	100	100	100
Suspended solids	5	5	5	5
Hardness (CaCO <sub>3</sub> )	25	25	25	25
pH, units:				
Cotton	6.5-10.0	9.0-10.5	2.5-10.5	7.5-10.0
Synthetics	6.5-10.0	3.0-10.5	(1)	6.5-7.5
Wool	6.5-10.0	3.0-5.0	2.5-5.0	3.5-6.0
Colour, units	5	5	5	5

(1) Not applicable.

#### **4 CRITERIA FOR PUBLIC WATER SUPPLIES (PWS)**

Criteria are given for public and private supplies from both surface and ground water sources.

Public supplies include water systems operated by municipalities, public utilities, industries, commissions, commercial establishments, etc. where competent operation of the water supply system is provided.

Private supplies include water systems operated by personnel who may not have the necessary technical or mechanical expertise.

##### **PWS-1 Criteria for Public Surface Water Supplies**

Since treatment processes exist which can convert any raw water (with a few minor exceptions) to potable water, it is necessary to define a commonly accepted treatment system which can produce a potable water at a reasonable cost. For the purposes of these criteria, such a system has been

defined to consist of coagulation, flocculation, sedimentation and rapid sand filtration; the use of chemicals is restricted by definition to the commonly used coagulants and chlorine for disinfection.

Two types of criteria have been established, namely the Permissible Criteria and the Desirable Criteria (Table PWS-1). Waters meeting both of these criteria are acceptable for treatment by the defined treatment process stated above. Waters meeting the Desirable Criteria provide for a greater margin of safety.

It should be borne in mind that the values given under the Permissible Criteria cannot be considered as maximum single sample values. These criteria should not be exceeded over substantial portions of time. If this should occur, then it will become necessary to determine the cause and initiate corrective action. The frequency and variety of sampling should be based on the findings of a comprehensive pollution survey.

**TABLE PWS-1**  
**WATER QUALITY CRITERIA FOR**  
**PUBLIC SURFACE WATER SUPPLIES**  
(Unless otherwise indicated, units are mg/l)

Constituent or Characteristic	Permissible Criteria	Desirable Criteria
<b>Physical</b>		
Colour (platinum-cobalt)	75 units	< 5 units
Odour	Readily removable by defined treatment	Absent
Turbidity	— do —	Absent
Temperature	85°F	Pleasant tasting
<b>Inorganic Chemicals</b>		
Ammonia	0.5 (as N)	< 0.01
Arsenic*	0.05	Absent
Barium*	1.0	Absent
Boron*	1.0	Absent
Cadmium*	0.01	Absent
Chloride*	250	< 25
Chromium* (hexavalent)	0.05	Absent
Copper*	1.0	Virtually absent
Dissolved Oxygen	≥ 4 (monthly mean) ≥ 3 (individual sample)	Near saturation
Fluoride*	See footnote (1)	1.0
Hardness*	Acceptable levels will vary with local hydrogeologic conditions and consumer acceptance.	
Iron (filterable)	0.3	Virtually absent
Lead*	0.05	Absent
Manganese* (filterable)	0.05	Absent
Nitrate plus Nitrite*	10 (as N)	Virtually absent
pH range	6.0 - 8.5 units	Least amount of interference with treatment process
Phosphorus* (phosphates)	Not encourage growth of algae or interfere with treatment process	
Selenium*	0.01	Absent
Silver*	0.05	Absent
Sulphate*	250	< 50
Total Dissolved Solids* (filterable residue)	500	< 200
Uranyl Ion*	5	Absent
Zinc*	5	Virtually absent
<b>Organic Chemicals<sup>(2)</sup></b>		
Carbon chloroform extract* (CCE)	0.15	< 0.04
Cyanide*	0.20	Absent
Methylene blue active substances*	0.5	Virtually absent
Oil and grease*	Virtually absent	Absent

Table PWS-1 (cont.)

Constituent or Characteristic	Permissible Criteria	Desirable Criteria
<b>Pesticides:</b>		
Aldrin*	0.017	— do —
Chlordane*	0.003	— do —
DDT*	0.042	— do —
Dieldrin*	0.017	— do —
Endrin*	0.001	— do —
Heptachlor*	0.018	— do —
Heptachlor epoxide*	0.018	— do —
Lindane*	0.056	— do —
Methoxychlor*	0.035	— do —
Organic phosphates plus carbamates*	0.1	— do —
Toxaphene*	0.005	— do —
<b>Herbicides:</b>		
2,4-D plus 2,4,5-T, plus 2,4,5-TP*	0.1	— do —
Phenolic Substances*	Virtually absent	— do —
<b>Radioactivity</b>		
	(pc/l)	(pc/l)
Gross beta*	1,000	< 100
Radium-226*	3	< 1
Strontium-90*	10	< 2
<b>Microbiological <sup>(1)</sup></b>		
Coliform organisms (at 35°C)	5,000/100 ml	< 100/100 ml
Fecal coliforms (44.5°C)	500/100 ml	< 10/100 ml
Fecal streptococci (35°C)	50/100 ml	< 1/100 ml
Total Bacteria (20°C)	100,000/100 ml	< 1,000/100 ml
Clostridia (in water) (35°C)	50/100 ml	0/100 ml

\* The defined treatment process has little effect on the constituents.

- (1) Annual Avg. of Max. Daily Air Temp. F.  
 50.0 to 53.7  
 53.8 to 58.3  
 58.4 to 63.8

Recommended Limit for Fluoride mg/l  
 1.7  
 1.5  
 1.3

- (2) Organic chemicals should not be present in concentrations as to cause adverse tastes and odours which cannot be removed by the defined treatment and/or by chlorination only.
- (3) A monthly geometric mean of the results of raw water samples collected on a weekly basis (minimum of one sample per week) should be less than the numbers given under the Permissible Criteria column. These figures do not imply a relationship between bacterial groups.

### PWS-2 Criteria for Public Ground Water Supplies

With the exception of dissolved oxygen, fluorides and microbiological criteria, the water quality criteria for surface water apply to ground water supplies.

For fluorides, hydrogen sulphide and pollution indicator organisms, the following apply to ground water supplies:

	<u>Permissible Criteria</u>	<u>Desirable Criteria</u>
	(Unless otherwise indicated, units are mg/l)	
Fluoride	2.4	1.0
Hydrogen Sulphide	0.1	Absent
Pollution Indicator Organisms	Coliform and other pollution indicator organisms should be virtually absent from all ground water supplies.	

It is considered desirable to provide the maximum of treatment — chlorination — for all ground water supplies. This measure ensures that nuisance organisms which exist in virtually all waters do not get the opportunity to develop a foothold in a water distribution system and thereby create objectionable conditions.

### PWS-3 Criteria for Private Water Supplies

The raw water available to private supplies such as individual dwellings, cottages, farms, etc., must be of such quality that it can be used in the raw state or be made acceptable for use with a minimum of treatment limited to disinfection, filtration and/or softening. Economic considerations and

lack of technical/mechanical expertise will prohibit the use of raw water supplies that require extensive treatment.

Some surface supplies have turbidities, colour and other undesirable constituents in excess of what can be used effectively in home or farm operations. Some ground water supplies (wells and springs) harbour objectionable gases, nuisance bacteria, in addition to having high concentrations of iron and being highly mineralized. The initial approach in establishing a private water supply should be to explore the ground water potential from the aspects of both quality and quantity. In many instances, deficiencies in ground water quality can be offset at a relatively low cost compared to that for surface waters.

Criteria for private water supplies are identical to the surface water criteria for public water supplies, with the exception of fluorides, hydrogen sulphide, physical and microbiological characteristics. For fluorides and hydrogen sulphide, the applicable criteria appear in Section PWS-2.

#### Physical Criteria:

The water supply should be substantially free from substances offensive to sight, taste or smell. Threshold odour values in excess of three units are generally considered objectionable.

Colour in the water supply should not exceed 15 units (platinum-cobalt scale).

Turbidity should be less than five units. Turbidities of up to 20 units may be removed relatively easily by sand or diatomaceous earth filters.

#### Microbiological Criteria:

<u>Microorganisms</u>	<u>Permissible Criteria</u>		<u>Desirable Criteria</u>
	<u>Chlorination only</u>	<u>Chlorination &amp; Filtration</u>	<u>No Treatment</u>
Coliforms (35°C)	100/100 ml	400/100 ml	0/100 ml
Fecal Coliforms (44.5°C)	10/100 ml	40/100 ml	0/100 ml
Enterococci (35°C)	1/100 ml	4/100 ml	0/100 ml
Total Bacteria (20°C)	1000/100 ml	4000/100 ml	10/100 ml
Clostridia (in water) (35°C)	0/100 ml	4/100 ml	0/100 ml

Raw water samples should be collected at least monthly. The Geometric Mean of sample results should not exceed the values given in the table above.

## 5 CRITERIA OF WATER QUALITY FOR AESTHETICS AND RECREATION (A & R)

All surface waters should be capable of supporting life forms of aesthetic value. The positive aesthetic and recreational values of water should be attained through continuous enhancement of water quality. Surface waters should be of such quality as to provide for the enjoyment of recreational activities such as hunting and fishing which are based on the utilization or consumption of fish, waterfowl and other forms of life.

The aesthetic and recreational values of unique or outstanding waters should be recognized and protected by development of appropriate water quality standards for each individual case. To retain or establish unspoiled wilderness values, it may be necessary to control access by mechanized methods of transportation.

General criteria for recreation and aesthetic use and specific criteria for total body contact recreation follow:

### A & R-1 General Criteria for Recreation and Aesthetics

Surface waters should be free of substances attributable to discharge of waste or land drainage which may impair aesthetic or recreational use, as follows:

- (1) Materials that will settle to form objectionable deposits.
- (2) Floating debris, oil, scum and other matter.
- (3) Substances producing objectionable colour, odour, taste or turbidity.
- (4) Materials, including radionuclides, in concentrations or combinations which are toxic or which produce undesirable physiological responses in humans, fish and other life and plants.
- (5) Substances, including nutrients, and conditions, including temperature, or combinations thereof in a degree or concentration which produces undesirable types or abundance of aquatic life.

### A & R-2 Criteria for Total Body Contact Recreation

Surface waters for total body contact recreational use should be free of substances attributable to discharge of waste or land drainage as follows:

- (1) Materials which will cause the pH to change beyond the range 6.5-8.3.
- (2) Materials which will obscure visibility in the water. In designated swimming and diving areas, clarity should be such that a Secchi Disc on the bottom is visible from the surface.
- (3) Conditions which will cause the water temperature to exceed 85°F.
- (4) Microbiological Criteria

Water used for body contact recreational activities should be free from pathogens including any bacteria, fungi or viruses that may produce enteric disorders or eye, ear, nose, throat and skin infections. Where ingestion is probable, recreational waters can be considered impaired when the coliform, fecal coliform, and/or enterococcus geometric mean density exceeds 1000, 100 and/or 20 per 100 ml respectively, in a series of at least ten samples per month, including samples collected during week-end periods.

If these criteria are exceeded, it will become necessary to determine the cause and initiate corrective action.

When evaluating a given area of water for recreational use, the appropriate numbers of samples, and the choice of tests to be performed should be determined by consultation between sampler and analyst, prior to sampling. An effort should be made to increase utilization of the fecal coliform and enterococcus tests since these presently appear to be the more relevant guides to the bacterial quality of bathing waters.

## GLOSSARY OF TERMS

- Bioassay** — A controlled laboratory procedure which subjects live aquatic organisms to various environmental stresses.
- Effluent Requirements** — Numerical or verbal descriptions of the quality of a waste or drainage effluent at the point of discharge to a receiving water body, land disposal site or waste disposal well.
- Eutrophication** — The increase in the nutrient content of the natural waters of a lake or other body of water.
- Geometric Mean** — The  $n$ th root of the product of  $n$  observations. The equation for the geometric mean ( $G_x$ ) can be expressed as:
- $$G_x = \sqrt[n]{X_1 \cdot X_2 \cdot X_3 \cdot \dots \cdot X_n}$$
- or  $G_x = \text{antilog} \left( \frac{\log X_1 + \log X_2 + \dots + \log X_n}{n} \right)$
- Land Drainage** — Water that has drained from the land surface naturally or through man-made drainage systems.
- Milligrams per Litre (mg/l)** — A unit of measure expressing the concentration of a substance in a solution.
- Milligram equivalents per litre (mg. eq/l)** — A unit indicating the chemical equivalence of ions; derived by dividing the concentration of an ion in milligrams per litre by the combining weight of that ion.
- Note: combining weight =  $\frac{\text{atomic or molecular weight of ion}}{\text{ionic charge}}$
- Oligotrophic** — Waters with a small supply of nutrients and hence a small organic production; usually having abundant dissolved oxygen at all depths.
- Photosynthetic (adj.)** — Relating to the process by which the chlorophyll-bearing cells of green plants convert carbon dioxide ( $\text{CO}_2$ ) and water ( $\text{H}_2\text{O}$ ) into sugar ( $\text{C}_6\text{H}_{12}\text{O}_6$ ) and oxygen ( $\text{O}_2$ ) in the presence of light.
- Raw Water** — Surface or ground water, prior to treatment.
- Waste** — Liquid carrying unwanted materials or compounds resulting from human activities or enterprises to a point of discharge. The mixture may or may not have received treatment.
- Water Quality Criteria** — Numerical or verbal descriptions of the quality of water required for particular uses.
- Water Quality Standards** — Numerical or verbal descriptions of the quality of water required for a variety of uses in a given drainage system.

## REFERENCES

- Bernstein, L. (1967)—Quantitative Assessment of Irrigation Water Quality; Water Quality Criteria, ASTM STP 416, pp. 51-65.
- Hem, J. D. (1959)—Study and Interpretation of the Chemical Characteristics of Natural Water; U.S. Geol. Survey, Water-Supply Paper 1473.
- Lunin, J. (1967)—Water for Supplemental Irrigation; Water Quality Criteria, ASTM STP 416, pp. 66-78.
- McKee, J. E. and Wolf, H. W. (1963)—Water Quality Criteria; California State Water Quality Control Board, Publication No. 3-A.
- Federal Water Pollution Control Administration, U.S. Dept. of the Interior (1968)—Report of the Committee on Water Quality Criteria.
- U.S. Salinity Laboratory Staff, (1954)—Diagnosis and Improvement of Saline and Alkali Soils; U.S. Department of Agriculture Handbook No. 60.
- Wilcox, L. V. and Durum, W. H. (1967)—Quality of Irrigation Water; Irrigation of Agricultural Lands, American Society of Agronomy, No. 11, pp. 104-122.
- Wright Rain Ltd. (1956)—Sprinkler Irrigation Manual.





\*96936000009295\*